



**MINUTES  
TOWN OF AMHERST  
HISTORIC PRESERVATION COMMISSION MEETING  
December 12, 2023  
7:00 PM**

**ROLL CALL**

| <b>Attendee Name</b>     | <b>Organization</b> | <b>Title</b>         | <b>Status</b> | <b>Arrived</b> |
|--------------------------|---------------------|----------------------|---------------|----------------|
| Susan M. Palmer          | Town of Amherst     | Chairman             | Present       |                |
| Catherine Waterman-Kulpa | Town of Amherst     | Vice Chairman        | Present       |                |
| Jennifer D. Kensy        | Town of Amherst     | Member               | Present       |                |
| Mary Lou Mancuso         | Town of Amherst     | Member               | Present       |                |
| Brian Swartz             | Town of Amherst     | Member               | Present       |                |
| Norman J. Hirschey       | Town of Amherst     | Member               | Present       |                |
| Deborah Bruch Bucki      | Town of Amherst     | Councilmember        | Present       |                |
| Bryan Fadel              | Town of Amherst     | Sr. Clerk Typist     | Present       |                |
| James Quinn              | Town of Amherst     | Assistant Planner    | Present       |                |
| Nora B. Robshaw          | Town of Amherst     | Deputy Town Attorney | Present       |                |
| Dan Howard               | Town of Amherst     | Planning Director    | Late          | 7:10 PM        |

**MINUTES APPROVAL**

November 21, 2023 Minutes

Ms. Bucki requested the minutes be amended to reflect that she was excused from the November meeting. Mr. Swartz made a motion to approve the November 21, 2023 minutes as amended. The motion was seconded by Mr. Hirschey and carried. Ayes 5, Noes 0, Abstain 1 (Waterman-Kulpa).

|                  |                                          |
|------------------|------------------------------------------|
| <b>RESULT:</b>   | <b>APPROVED [5 TO 0]</b>                 |
| <b>MOVER:</b>    | Brian Swartz, Member                     |
| <b>SECONDER:</b> | Norman J. Hirschey, Member               |
| <b>AYES:</b>     | Palmer, Kensy, Mancuso, Swartz, Hirschey |
| <b>ABSTAIN:</b>  | Waterman-Kulpa                           |

## **NEW BUSINESS**

1. 400 MILL STREET (ST. MARY'S MOTHERHOUSE) - CERTIFICATE OF APPROPRIATENESS  
Gary Browne, The Browne Company, said one reason they want to move away from slate is due to safety; slate can slide off the roof and the owner want to use the courtyards. Another reason is that they are unsure if anyone will be able to repair slate in 10 years.

Mr. Browne said they prefer Contractor G because they put together the mockup, they are familiar with the site, they have been in business for 60 years and they have considerable experience with synthetic slate. He said he is not sure if they have worked with historic landmarks on the State and National Register before and he believes the 50-year warranty is the standard warranty. Ms. Waterman-Kulpa expressed concern that a standard warranty would be non-transferable should there be a change of ownership. Mr. Browne said that he believes the proposed synthetic slate has been on the market for close to 20 years.

Mr. Swartz said that St. Mary's Motherhouse is only a handful of buildings in the town that is listed as a local, state, and national historic landmark due to it maintaining most of its original features, including the original slate roof. He referenced National Park Service Preservation Briefs 4 (Roofing for Historic Buildings) and 29 (The Repair, Replacement and Maintenance of Slate Roofs), along with a June 19, 2019 article not recommending restoration using artificial mineral fiber slate due to its unnatural appearance, the possibility of fading, and it costing only marginally less than artificial slate over time.

Mr. Swartz made a motion to deny the use of an alternative material for the original slate roof. The motion was seconded by Ms. Waterman-Kulpa. Mr. Browne said that real slate also fades, that synthetic slate saves on labor costs due to it being easier to install, and that it also creates less waste. Ms. Waterman-Kulpa made a motion to amend the denial to include that the proposed material has not been around long enough to test its lifespan, the replacement with synthetic slate would preclude the owner's ability to obtain historic tax credits in the future and that the difference between the prices could be recouped through tax credits. Ms. Bucki inquired about whether the tax credits had been explored and Mr. Browne said they had, but would be unable to utilize them due to the setup of the ownership group. He also added that the proposed material is not mineral fiber slate. Mr. Hirschey said he believes the synthetic slate is a viable option. Ms. Palmer seconded Ms. Waterman-Kulpa's motion to amend and it carried. Ayes 6, Noes 0.

Mr. Swartz made a motion to deny the use of an alternative material as a replacement for the original slate roofing material at St. Mary's Motherhouse as amended. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 4, Noes 1 (Hirschey), Abstain 1 (Mancuso).

Ms. Waterman-Kulpa made a motion to refer the matter of the partially replaced roof without proper permits to the Building Department. The motion was seconded by Mr. Swartz and carried. Ayes 5, Noes 1 (Hirschey).

**RESULT:** DENIED [4 TO 1]  
**MOVER:** Brian Swartz, Member  
**SECONDER:** Catherine Waterman-Kulpa, Vice Chairman  
**AYES:** Palmer, Waterman-Kulpa, Kensy, Swartz  
**NAYS:** Hirschey  
**ABSTAIN:** Mancuso

2. 2024 MEETING SCHEDULE

Ms. Palmer made a motion to approve the 2024 meeting schedule. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 6, Noes 0.

**RESULT:** APPROVED [UNANIMOUS]  
**MOVER:** Susan M. Palmer, Chairman  
**SECONDER:** Catherine Waterman-Kulpa, Vice Chairman  
**AYES:** Palmer, Waterman-Kulpa, Kensy, Mancuso, Swartz, Hirschey

3. 2023 BUDGET

Ms. Palmer made a motion to approve spending a portion of the 2023 budget on two historic property plaques and a 2024 Protector Circle membership with Preservation Buffalo Niagara. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 6, Noes 0. Ms. Kensy made a motion to approve a portion of the 2023 budget for a one-year membership with the National Alliance of Preservation Commissions. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 6, Noes 0.

**RESULT:** APPROVED [UNANIMOUS]  
**MOVER:** Susan M. Palmer, Chairman  
**SECONDER:** Catherine Waterman-Kulpa, Vice Chairman  
**AYES:** Palmer, Waterman-Kulpa, Kensy, Mancuso, Swartz, Hirschey

## **OLD BUSINESS**

4. 2024 COMMISSION MEMBERSHIP

The Commission held an executive session to interview a candidate for an open seat on the Historic Preservation Commission.

Ms. Waterman-Kulpa made a motion to recommend Jeffery Amplement as a candidate for the Historic Preservation Commission with a term starting in January 2024. The motion was seconded by Ms. Palmer and carried. Ayes 6, Noes 0.

**RESULT:** APPROVED [UNANIMOUS]  
**MOVER:** Catherine Waterman-Kulpa, Vice Chairman  
**SECONDER:** Susan M. Palmer, Chairman  
**AYES:** Palmer, Waterman-Kulpa, Kensy, Mancuso, Swartz, Hirschey

5. 2023 ANNUAL REPORT

Mr. Hirschey made a motion to approve the 2023 annual report. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 6, Noes 0.

**RESULT:** APPROVED [UNANIMOUS]  
**MOVER:** Norman J. Hirschey, Member  
**SECONDER:** Catherine Waterman-Kulpa, Vice Chairman  
**AYES:** Palmer, Waterman-Kulpa, Kensy, Mancuso, Swartz, Hirschey

6. CHATEAU TERRACE - HISTORIC DISTRICT

Mr. Swartz said he had discussed the procedure for potentially hiring a consultant to complete the historic district application with Mr. Howard and Mr. Quinn. He said they are looking into a consultant since the amount of work and time needed for the project would not fulfill the role of an intern. Mr. Howard confirmed that the use of a consultant would utilize funds in the Commission's annual budget.

**RESULT: NO ACTION**

7. 22 CHATEAU TERRACE - GARAGE DEMOLITION REFERRAL  
Ms. Palmer made a motion to adjourn. The motion was seconded by Ms. Waterman-Kulpa and carried. Ayes 6, Noes 0.

**RESULT: ADJOURNED**

8. LOCAL LANDMARK PLAQUES  
Ms. Palmer said she had not received any response from the owners of 38 Richfield Road, but had spoken to owners of the Hedstrom Gatehouse. Ms. Mancuso said the Hedstrom Gatehouse was not one of the locations she had visited, but said she had spoken to the owner who confirmed that the property already has a plaque. She also mentioned that the owners of 38 Richfield were interested in a plaque. Mr. Hirschey said he would follow up with the Haussauer House owners as discussed at the previous meeting. Mr. Howard suggested that the Commission consider having anyone receiving a plaque sign documents that covered any requirements the Commission might have and would also serve as a record that they had received the plaque. Ms. Palmer said the plaques are an opportunity to show owners of historic properties appreciation for owning and maintaining the properties and does not believe they should include any enforceable or binding conditions. She suggested that the Attorney's office come up with a letter to submit to recipients.

**RESULT: NO ACTION**

9. UPDATE ON CLG GRANT SUBMISSION / PRESERVATION DAY  
Ms. Palmer asked Mr. Quinn to check on reimbursements and payments made for Preservation Day. Mr. Quinn also confirmed that he has everything needed to close out the CLG grant.

**RESULT: NO ACTION**

10. EDUCATION PLAN - WEBSITE PLAN, PRESENTATIONS  
Mr. Quinn said an updated list of landmarks is available on the website and he is in the process of updating the names of the Commission. Mr. Swartz offered to meet with Mr. Quinn to go over captions and placement of pictures. Ms. Palmer said she needs Ms. Waterman-Kulpa's summary training form for the year.

**RESULT: NO ACTION**

## **MISCELLANEOUS**

The Commission recognized Ms. Bucki for serving as the Historic Preservation Commission liason the last six years and Ms. Palmer for serving as the Commission chair the last four years.

## **ADJOURNMENT**

The Historic Preservation Commission meeting of December 12, 2023 was adjourned at 8:49pm.



**MINUTES  
TOWN OF AMHERST  
HISTORIC PRESERVATION COMMISSION MEETING  
November 21, 2023  
7:00 PM**

**ROLL CALL**

| <b>Attendee Name</b>     | <b>Organization</b> | <b>Title</b>         | <b>Status</b> | <b>Arrived</b> |
|--------------------------|---------------------|----------------------|---------------|----------------|
| Susan M. Palmer          | Town of Amherst     | Chairman             | Present       |                |
| Catherine Waterman-Kulpa | Town of Amherst     | Vice Chairman        | Absent        |                |
| Jennifer D. Kensy        | Town of Amherst     |                      | Present       |                |
| Mary Lou Mancuso         | Town of Amherst     |                      | Present       |                |
| Brian Swartz             | Town of Amherst     |                      | Present       |                |
| Norman J. Hirschey       | Town of Amherst     |                      | Present       |                |
| Deborah Bruch Bucki      | Town of Amherst     | Councilmember        | Excused       |                |
| Bryan Fadel              | Town of Amherst     | Sr. Clerk Typist     | Present       |                |
| James Quinn              | Town of Amherst     | Assistant Planner    | Present       |                |
| Nora B. Robshaw          | Town of Amherst     | Deputy Town Attorney | Present       |                |
| Dan Howard               | Town of Amherst     | Planning Director    | Present       |                |

**MINUTES APPROVAL**

October 10, 2023 Minutes

Attachment: HPC Minutes 112123 (28303 : November 21, 2023 Minutes)

**RESULT:**           **APPROVED [4 TO 0]**  
**AYES:**           Kensy, Mancuso, Swartz, Hirschey  
**ABSTAIN:**       Palmer  
**ABSENT:**       Waterman-Kulpa

## **NEW BUSINESS**

1.     400 MILL STREET (ST. MARY'S MOTHERHOUSE) - CERTIFICATE OF APPROPRIATENESS  
 Ms. Palmer said she felt it was not clear what was being requested. She added that the applicant agreed to adjourn the matter so that they can submit an executive summary clearly identifying what they are asking for and to give the members ample time to review the materials before the next meeting.

**RESULT:**           **ADJOURNED**

2.     2024 COMMISSION MEMBERSHIP  
 Ms. Palmer said that there will definitely be two open Commission seats next year, including historian, and possibly a third open seat for architect. She suggested a press release be added to the town website as they did last year. She also said that it has already been posted in the American Institute of Architects and that they will also be posting in the Amherst Bee. The Commission also suggested reaching out to Preservation Buffalo Niagara and Buffalo Niagara Heritage Village to see if there might be any other opportunities for outreach.
3.     2023 ANNUAL REPORT  
 Ms. Palmer explained that there are two annual reports that the Historic Preservation Commission completes; one for Certified Local Governments and one required by the HPC rules. Ms. Palmer presented her draft for the latter and members made suggestions.

## **OLD BUSINESS**

4.     CHATEAU TERRACE - LOCAL DISTRICT NOMINATION  
 Mr. Swartz said that he and Ms. Waterman-Kulpa met briefly to discuss a plan to move the nomination forward. He said that there will be a tremendous amount of work involved to make a usable document for the Town Board to make a decision. He suggested spending some of their budget next year to employ an intern to complete blue forms for each property within the district and the other members agreed.
5.     22 CHATEAU TERRACE - GARAGE DEMOLITION REFERRAL  
 Ms. Palmer made a motion to adjourn. The motion was seconded by Mr. Swartz and carried. Ayes 5, Noes 0, Absent 1 (Waterman-Kulpa).

**RESULT:**           **ADJOURNED**

6.     LOCAL LANDMARK PLAQUES - HARLEM ROAD SCHOOL & MAIN STREET ENTRANCEWAYS  
 Mr. Quinn said he will forward the scope of work to get the Harlem Road School plaque installed, but they still need to figure out where the plaque will be installed for the Main Street entranceways. Mr. Swartz said that he doesn't believe the plaque will last if installed directly on the street furniture masonry and said they should consider alternative options, such as an adjacent sign. Mr. Howard recommended working with someone who has experience with the street furniture materials and said he and Mr. Quinn will see if they have any open contracts that could include the installation of the street furniture plaque on.  
 Ms. Palmer mentioned how Park School and St. Mary's were preferred options for additional plaques, but she recommended pursuing other options due to time constraints in regards to encumbering funds. The Commission agreed on Haussauer house (1000 North Forest) and 38 Richfield as substitutes. The Commission also discussed Preservation Buffalo Niagara membership options next year.
7.     UPDATE ON CLG GRANT SUBMISSION / PRESERVATION DAY

Mr. Quinn said they just need to submit the narrative and budget.

8. EDUCATION PLAN - WEBSITE PLAN, PRESENTATIONS

Ms. Palmer said that they have one more training from Preservation Buffalo Niagara next year and that she sent Mr. Quinn comments regarding changes to the website along with pictures that need to be added.

**MISCELLANEOUS**

**ADJOURNMENT**

The Historic Preservation Commission meeting of November 21, 2023 was adjourned at 8:06pm.

***St. Mary's Commons Apartments, L.P.***  
*2001 Marcus Avenue, Suite N-118*  
*Lake Success, NY 11042*

September 29, 2023

Town of Amherst Planning Department  
 5583 Main Street  
 Williamsville, NY 14221

Re: St. Mary's Apartments-400 Mill Street  
 Amherst Historic Preservation Commission  
 Application For Certificate of Appropriateness  
 Architectural Review

Dear Town of Amherst Planning Department:

Enclosed please find an Application for Certificate of Appropriateness and the requested documents. By way of background, St. Mary's is an affordable senior housing community. In recent years, the roof system experienced a number of failures, including roof leaks. The roof is in desperate need of repairs and replacement. We hired Gary Browne as our roof consultant.

Contact details for Mr. Browne are as follows:

Roof Consultant

Gary Browne, Roof Consultant  
 The Browne Company  
 98 Forest Drive  
 Orchard Park, NY 14127  
 Office: 716-667-0802  
 Cell: 716-628-7922  
[browneco@verizon.net](mailto:browneco@verizon.net)

- 1) As requested, we have enclosed the following materials.
- 2) Detailed written description of all the proposed work. Please see the detailed scope in the attached bid package.
- 3) Color Photographs. Please see color photographs attached.
- 4) Current Property Boundary Survey-A survey is attached.
- 5) Building Drawing Set-Building Drawings are attached.
- 6) Manufacturer's literature from EcoStar, the manufacturer of the synthetic slate.
- 7) Manufacturer's literature from CertainTeed, the manufacturer of the Grand Manor shingles we would like to use everywhere else on the building.
- 8) Specifications and drawings for roof replacement work.

Should you have any questions, please feel free to reach out to Skip Cerio (cell: 716-864-6477) or Tom Granville (cell: 516-659-9692). Thank you in advance for your time in connection with this Application.

By: St. Mary's Commons Apartments, L.P.

By: St. Mary's Commons Associates, L.L.C.

By: 

Thomas G. Granville  
Its Manager

Date: September 29, 2023

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**OFFICIAL USE ONLY**

Received By: \_\_\_\_\_  
 Date Received: \_\_\_\_\_  
 Date to AHPC: \_\_\_\_\_  
 Application Complete: \_\_\_\_\_  
 Date AHPC Approved: \_\_\_\_\_  
 Date AHPC Denied: \_\_\_\_\_

**AMHERST HISTORIC PRESERVATION COMMISSION  
 APPLICATION FOR CERTIFICATE OF APPROPRIATENESS -  
 ARCHITECTURAL REVIEW**

Pursuant to Chapter 121 of the Town of Amherst Code

**SUBMITTAL PROCESS:**

1. Apply for a Building or Demolition Permit and obtain zoning compliance approval from the Town Building Department.
2. Submit a complete Application for Certificate of Appropriateness with all required information from the checklist below to the Town Planning Department before the submittal deadline.

**PROPERTY INFORMATION:**

Address: St. Mary's Apartments, 400 Mill Street, Amherst NY 14221

**BRIEF DESCRIPTION OF SCOPE OF WORK:**

The existing roof system is failing and the roof is in desperate need of repair. We are proposing a full roof replacement. Existing slate would be replaced with either slate, synthetic slate, or high-end, slate-like architectural asphalt shingles.

**APPLICANT:** Name/Company Name: St. Mary's Commons Apartments L.P.

Telephone Number: 516-352-6100 Ext 2 Email Address: granvill@whitneycap.com

Street Address, City and Zip Code: 2001 Marcus Ave Suite N118, Lake Success, NY 11042, ATTN Thomas Granville

**PROPERTY OWNER (IF DIFFERENT FROM APPLICANT):**

Name/ Company Name: Same as above

**ROOF CONSULTANT INFORMATION:**

Name/ Company Name: The Browne Company Roofing & Waterproofing Consultants, Inc.  
 Telephone Number: 716-667-0802

Email Address: Browneco@verizon.net, ATTN Gary Browne

Street Address, City and Zip: 98 Forest Drive, Orchard Park, NY 14127

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**WHO IS COMPLETING THE WORK****Applicant (if different from Owner): Yes/ No****Contractor: Yes/ No****PROJECT DESCRIPTION CHECKLIST:****By attachment to this application, provide all of the following****items:** Detailed written description of all proposed work. This should include a description of all proposed additions, proposed demolition of a portion or the entire building, proposed removal of materials/design elements, proposed addition of materials/design elements, and/or a new building. Please include a description of how work will be conducted.

- ☐ **Color Photographs:** Photographs of the building and site. Include overall elevation views and close-ups of all affected areas being modified. Include historic photos (if available.) Digital images submitted electronically are preferred.
- ☐ **Current Property Boundary Survey.**
- ☐ **Building Drawing Set:** Including scaled and dimensioned elevations indicating all exterior building materials and finishes to be used, floor plans, and roof plan. For changes and additions, the drawing set must show existing and proposed conditions.
- ☐ **Perspective Drawings/Color Rendering.**
- ☐ **Site Layout Plan:** Where demolition of a portion or the entire building is proposed, and/or an addition is proposed, and/or new building is proposed.
- ☐ **Samples** and description of materials and colors being proposed. (Indicate by manufacturer's name/color/number.)
- ☐ Provide all other information which the Commission may deem necessary in order to visualize/understand the proposed scope of work.

By signing below, I attest that I have read and do understand the above Review Procedures for Certificates of Appropriateness. I also agree that all information submitted on this application is true and accurate to the best of my knowledge.

**By: St. Mary's Commons Apartments L.P.**

Signature of Applicant

Date

Thomas G. Granville

Print Name

**FOUR (4) copies of this form and all supporting documents must arrive by 4:00 pm (end of day) two weeks prior to the monthly Historic Preservation Commission meeting. Upon submission of the complete application, one complete PDF shall be emailed to the Town of Amherst. Email address shall be provided at the time of submission.**

**DO NOT WRITE BELOW THIS LINE**

**The Town of Amherst Historic Preservation Commission has reviewed this application and has determined the following:**

                     **Approved**

**Approved with Conditions**

## Denial

**Conditions/Comments:**

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.

AHPC Chairperson's Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**Approval of the Certificate of Appropriateness shall be in addition to and not in lieu of any building permits that may be required.**

Town of Amherst Planning Department, 5583 Main Street Williamsville New York 14221  
Phone (716) 631-7051 Fax (716) 631-7153 Web [www.amherst.ny.us](http://www.amherst.ny.us)

**THE BROWNE COMPANY**  
*Roofing and Waterproofing Consultants, Inc.*  
98 Forest Drive  
Orchard Park, New York 14127  
Phone/Fax (716) 667-0802  
email: browneco@verizon.net

**INVITATION TO BID**

**ST. MARY'S COMMONS APARTMENTS  
ROOF REHABILITATION PROJECT  
400 Mill Street, Williamsville, NY  
September 14, 2023**

You are invited to bid on St. Mary's Commons Apartments Roof Rehabilitation Project, 400 Mill Street, Williamsville, NY. Bids shall be submitted as per the Bid Form.

Mr. Shawn Crawford, Whitney Management Corp. will receive bids until 3:00 P.M. local time on October 5, 2023, at his office, 9575 Katy Freeway, Suite 330, Houston, TX 77024. Bids may be emailed to Mr. Crawford at SCrawford@whitneymgmt.com. Bids received after this time will not be accepted. Bids will be opened privately.

A pre-bid meeting and job walk will be held at 11:00 A.M. on September 21, 2023, at the project site, 400 Mill Street, Williamsville, NY. Bidders to meet at the west parking lot. All parties interested in bidding on this Project should attend!

Bidding Documents will be distributed at the pre-bid meeting.

Bidding Documents, in good condition, must be returned to the Owner within 10 days of the bid opening.

St. Mary's Commons Apartments reserves the right to waive irregularities and to reject any and all bids.

Respectfully submitted

THE BROWNE COMPANY

Mr. Gary Browne, Roof Consultant

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

## TABLE OF CONTENTS

### **00010 PRE-BID INFORMATION**

- Invitation to Bid

### **00100 INSTRUCTIONS TO BIDDERS**

- Supplementary Instructions to Bidders
- Contract Time
- Pre-Bid Meeting and Job Walk
- Insurance Requirements
- Miscellaneous Provisions
- Applications for Payment
- Alternate Prices
- Allowances
- Coordination
- Quality Control
- Protection and Use of Facilities
- Regulations & Safety
- Contract Closeout

### **00300 BID FORMS**

- Affidavit Regarding Collusion

### **DIVISION 7 - THERMAL & MOISTURE PROTECTION**

- Section 07300 – Slate Shingles and Related Work (Base Bid No. 1)
- Section 07310 – Synthetic Slate Shingles and Related Work (Base Bid No. 2)
- Section 07311 – Asphalt Shingles and Related Work (Base Bid No. 3)
- Section 07460 – Fiber Cement Siding
- Section 07530 – Fully Adhered EPDM Roofing
- Section 07620 - Sheet Metal Flashing and Trim
- Section 07711 – Roof and Gutter Cable Deicing System

**DOCUMENT 00100****INSTRUCTION TO BIDDERS****1.01 DOCUMENT INCLUDES**

- A. Related documents, bid submission, intent, contract time, definitions, contract documents identification, availability of documents, inquiries/addenda, product/assembly/system substitutions, site examination, qualifications, bid ineligibility, submission procedure, bid form signature, additional bid information, duration of offer, acceptance of offer.

**1.02 RELATED DOCUMENTS**

- A. AIA Document A701 - Instructions to Bidders
- B. Document 00800 - Supplementary Conditions

**1.03 BID SUBMISSION**

- A. Offers signed, executed, and dated will be received Mr. Shawn Crawford, Whitney Management Corp. will receive bids until 3:00 P.M. local time on October 5, 2023, at his office, 9575 Katy Freeway, Suite 330, Houston, TX 77024. Bids may be emailed to Mr. Crawford at SCrawford@whitneymgmt.com. Bids received after this time will not be accepted. Bids will be opened privately.

**1.04 INTENT**

- A. The intent of this bid call is to obtain an offer for the St. Mary's Commons Apartments Roof Rehabilitation Project, 400 Mill Street, Williamsville, NY, for a Stipulated Sum contract in accordance with the Contract Documents.

**1.05 CONTRACT TIME**

- A. Perform the Work in 180 calendar days. The bidder in submitting an offer, accepts the Contract Time period stated for performing the work.
- B. The owner required that under the work of this contract be completed as quickly as possible. Consideration may be given to time of completion when reviewing the submitted Bids.

**1.06 DEFINITIONS**

- A. Bid Documents: Contract Documents supplemented with Instructions to Bidders, Bid Form and Appendices, and Bid Securities identified.
- B. Contract Documents: Defined in AIA A101 Article 7 including issued addenda.
- C. Bid, Offer, or Bidding: Act of submitting an offer.

- D. Contract Sum: Monetary price identified by the bidder in the Bid Form.
- E. Acceptable: Satisfactory to and approved by the Consultant and by the Owner.
- F. Approved: Allowable and acceptable by the Consultant and by the Owner.
- G. Directed: Instructed by the Consultant or the Owner.
- H. Reviewed: Examined by the Consultant and by the Owner for purpose of approval.
- I. Unacceptable: Not satisfactory to the Consultant or Owner.
- J. Installer: A person, firm, or corporation who unloads, unpacks, assembles, erects, applies, places, finishes, cures, protects, adjusts, and cleans Products.
- K. Manufacturer: A person, firm, or corporation who makes Products.
- L. System: Products or assemblies that are fit together and integrated to function as a useful or operational apparatus.
- M. Project Manual: Is the volume assembled for the Work, which includes the Bid Documents, Contract Documents, and Specifications.

#### 1.07 CONTRACT DOCUMENT IDENTIFICATION

- A. The Contract Documents are identified as St. Mary's Commons Apartments Roof Rehabilitation Project, 400 Mill Street, Williamsville, NY, as prepared by The Browne Company Roofing and Waterproofing Consultants, Inc., located at 98 Forest Drive, Orchard Park, NY.

#### 1.08 AVAILABILITY OF DOCUMENTS

- A. Bid Documents are attached herein.
- B. Bid Documents must be returned complete and undamaged to the Owner, within 10 days of bid opening.

#### 1.09 INQUIRIES/ADDENDA

- A. Direct questions to the Consultant at (716) 667-0802.
- B. Addenda may be issued during the bidding period. All Addenda become part of the Contract Documents. Include resultant costs in the Bid Price.

#### 1.10 PRODUCT/ASSEMBLY/SYSTEM SUBSTITUTIONS

- A. Where the Bid Documents stipulate a particular Product, substitutions will be considered by the Consultant up to 5 days before receipt of bids. Bidders shall include in their substitution request any changes required in the Work to accommodate such substitutions.

#### 1.11 SITE EXAMINATION

- A. A pre-bid meeting and job walk will be held at 11:00 A.M. on September 21, 2023, at the project site, 400 Mill Street, Williamsville, NY. Bidders to meet at the west parking lot. Bidders wishing to submit offers should attend.

#### 1.12 QUALIFICATIONS

- A. To demonstrate qualifications for performing the Work of this contract, Bidders may be requested to submit written evidence of financial position, previous experience, current commitments, etc.

#### 1.13 SUBMISSION PROCEDURE

- A. Submit on copy of the executed offer on the Bid Forms provided, signed and sealed with the proper Bid Security in a closed opaque envelope, clearly identified with bidder's name, project name, and Owner's name on the outside.

#### 1.14 BID INELIGIBILITY

- A. Bids that contain irregularities of any kind, may be declared unacceptable at the discretion of the Owner.

#### 1.15 BID SECURITY DEPOSIT

- A. Not Required

#### 1.16 PERFORMANCE BONDS

- A. Not Required

### 1.17 BID FORM SIGNATURE

A. The Bid Form shall be signed by the bidder as follows:

1. Sole Proprietorship: Signature of sole proprietor in the presence of a witness who will also sign. Insert the words "Sole Proprietorship" under the signature.
2. Partnership: Signature of all partners in the presence of a witness who will also sign. Insert the word "Partner" under each signature.
3. Corporation: Signature of a duly authorized signing officer(s) in their normal signatures. Insert the officer's capacity in which the signing officer acts, under each signature. Affix the corporate seal. If the bid is signed by officials other than the president and secretary of the company, or the president / secretary / treasurer of the company, a copy of the by-law resolution of their board of directors authorizing them to do so, must also be submitted with the Bid Form in the bid envelope.
4. Joint Venture: Each party of the joint venture shall execute the Bid Form under their respective seals in a manner appropriate to such party as described above, similar to the requirements of a Partnership.

### 1.18 INSURANCE REQUIREMENTS

- A. No work may commence prior to receipt of Certificate of Insurance from the Contractor showing St. Mary's Commons Apartments and The Browne Company as additional insureds with no less than a minimum comprehensive public liability amount of \$1,000,000 and a minimum 30 days prior written notice of cancellation to the certificate holder. "Claims made" type policies are unacceptable.
- B. Business Liability policy must list "Roofing" as the primary trade of the Contractor and/or Sub-Contractor on the declaration page of the policy.
- C. Contractor shall carry New York State mandated workers' compensation insurance in statutory amounts covering all the contractor's and subcontractor's employees and shall submit written evidence of compliance.
- D. Contractor shall save harmless St. Mary's Commons Apartments and The Browne Company from all damage and claims for damage, demands, suits, costs, recoveries and judgments which may be recovered against St. Mary's Commons Apartments and The Browne Company or their officers, agents or employees caused by Contractor acts or omissions in performing a contract arising or growing out of the performance of this contract.

### 1.19 DURATION OF OFFER

- A. Bids shall remain open to acceptance and shall be irrevocable for a period of thirty (30) calendar days after the bid closing date.

### 1.20 ACCEPTANCE OF OFFER

- A. The owner reserves the right to accept or reject any or all bids.

### 1.21 EXISTING CONSTRUCTION VERIFICATION

- A. Before submitting his bid, the Contractor shall visit the project site and verify conditions, locations, and dimensions of all existing equipment, the structure, and the site conditions that pertain to this installation.
- B. The details shown and the information provided are not represented or guaranteed by the Owner or the Roof Consultant as being accurate as to the actual "as built" and present conditions. Bidding Contractor shall verify all conditions at the site and perform all work to complete the project under this contract, regardless of the variations that may be found, without additional cost to the Owner.

### 1.22 MISCELLANEOUS PROVISIONS

- A. The buildings having work done to their roofs will not be occupied during the Work. Access to the Building Roofs will be from the exterior of the building.
- B. Owner will not be supplying any materials or equipment to complete the Work.
- C. Contractor to pay all applicable New York State Sales Tax.
- D. Contractor's staging area, access areas, and parking areas will be determined, and approved, by the Owner prior to Contract award and before work commences.
- E. Contractor may only work between the hours of 9:00 A.M. and 2:00 P.M, unless specific permission is granted to work later in the afternoon. Weekend work is not permissible.
- F. Contractor to obtain and pay for all building, sidewalk, street permits, etc. that may be required by the Town of Amherst, NY.

### 1.23 APPLICATIONS FOR PAYMENT

- A. Contractor shall use AIA Document G702, Application and Certificate for Payment, and AIA Document G703, Continuation Sheet for submitting applications for payment.
- B. Contractor shall submit five (5) copies of application for payment, with original signatures and notarized, to the Consultant for review.
- C. Contractor shall submit application for payment to the Consultant by the 20th of the month so he can review and submit to Owner by the end of the month.
- D. Payments will be subject to the retainage of ten percent (10%) of the amount due for payment.
- E. Retainage shall not be released until approval by Owner of final completion.
- F. The Consultant will recommend the withholding of payments to protect the interest of the Owner if certain conditions are present, including:
  - 1. Damaged or non-conforming work requiring repair or correction.

2. Damaged property requiring repair or replacement.
3. Failure by the Contractor to meet specified Contract milestones or the Contractor's own approved schedule.
4. Claims made against the owner on account of the Contractor's failure to perform or furnish work without interference and damage to others.

#### 1.24 ALTERNATE PRICES

- A. The price of the Bid for each Alternate shall be filled-in in the appropriate space on the Bid Form. The price of the Bid for each Alternate will be the amount to be added or deducted from the Contract Sum of the Base Bid if the Owner selects the Alternate(s). The Owner may accept Alternates in any order, regardless of how they are listed, and determine the lowest responsible Bidder on the basis of the sum of the Base Bid plus any selected Alternates.
- B. Alternates shall include all costs for material, delivery, installation, taxes, overhead, profit, etc.
- C. There are no alternates on this project.

#### 1.25 ALLOWANCES

- A. Include in the Contract Sum all allowances stated in the Contract Documents. Allowances include specific cash amounts and quantities of work for certain scheduled items.
- B. Include the cash amount of \$10,000 in each Base Bid for repairs to the existing structural roof deck, wind uplift analysis, and any other additional work that may be required. Reimbursement to be as per the Unit Costs on the Bid Form times the quantity.
- C. Include the quantity allowance of 2,000 sq. ft. of wood deck replacement (match existing construction) in each base bid.

#### 1.26 COORDINATION

- A. The responsibility for the coordination and completion of the work in accordance with Contract Documents is upon the primary awarded Contractor with whom the Owner enters into a contract for the work herein described. Such terms as "roofer", "applicator", "other contractors", "by others" and similar expressions shall be deemed to refer to the Contractor with whom the Owner entered into agreement.
- B. Contractor must maintain a full-time supervisor/foreman on the job site during times that roofing work is in progress. This person shall have a minimum of ten years experience in roofing work similar in nature and scope to specified roofing. The person shall continue on the project through final acceptance, unless the person's performance on the project is not acceptably adequate or impedes project productivity.
- C. The Contractor shall submit to the Consultant a detailed work schedule prior to beginning work.

- D. Site will be available to Contractor upon receipt of the Owner's Notice to Proceed, unless otherwise indicated in these specifications. Care, custody, and control of the site work area, equipment area, and material storage area are vested in the Contractor during the term of operations under the Contract.
- E. Failure to examine the project building and the site and to become familiar with the existing conditions shall not constitute cause for complaint or claim for extra payment. Accept project site as it exists.
- F. Entrances or exits to or from the buildings shall not be blocked for any reason or hamper the normal operation of the building in any way unless permission is first obtained from the Owner. If streets or sidewalks are to be blocked, all necessary permits must be obtained from the appropriate governmental agency. Fire protections and immediate access for fire equipment must be maintained at all times.
- G. Equipment and material storage areas are limited to those designated by the Owner. Fencing of the ground work area will be required to keep unauthorized personnel out of the area, as well as an OSHA approved scaffold walkway protection system which must be erected underneath any roof hoisting equipment.
- H. Work that might interfere with the use of the facilities by the Owner and its occupants shall be accomplished at a time approved beforehand by the Owner.
- I. Contractor's staging area, access areas, and parking areas will be determined, and approved, by the Owner prior to Contract award and before work commences.
- J. Contractor must provide Owner with 24-hour emergency telephone numbers, in the event of a problem on an evening or weekend. Due to the critical nature of the Owner's operations, Contractor must respond to such emergencies, with qualified roofers on site, within 3 hours.

#### 1.27 QUALITY CONTROL

- A. If, in the opinion of the Contractor, any work indicated on drawings or specified in such a manner as to make it impossible to produce work of highest quality, the contractor shall advise the Roofing Consultant before proceeding. Should discrepancies appear from one drawing to another or between Drawings and Specifications, Contractor is to conclude that the more stringent requirement applies.
- B. Contractor shall possess/maintain, on site, a copy of specifications, MSDS sheets, related documents, all pertinent drawings, and any addendum information.
- C. Nothing in the specifications shall be construed as relieving Contractor of responsibility for the waterproof quality, for the roofing work, or for compliance with other requirements.
- D. The presence of an Owner representative or the Consultant's representative is not to relieve Contractor of his quality assurance, but to examine it.
- E. Project quality control is the Contractor's responsibility and obligation. Nothing contained herein or stated shall imply any obligation by the Owner or his representatives to Contractor by monitoring the work, nor shall monitoring of the work relieve Contractor of any responsibility under the terms of the Contract.

- F. Upon completion of all specified work items, a final roof inspection shall be performed. Those required to attend will include the Roofing Contractor and his on-site foreman/supervisor, the Roof Consultant, and a representative of the Owner. The Roof Consultant will coordinate the date of the final inspection with the Contractor and the Owner.
- G. Any deficiencies or incomplete work items will be noted at this time and documented. A punch list of all such items will be issued to the Contractor.
- H. Repair or replace (as required) deteriorated or defective work found at time above inspection to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements. The Contractor is to notify the Consultant's representative upon completion of corrections.

#### 1.28 PROTECTION AND USE OF FACILITIES

- A. **IT IS THE ROOFING CONTRACTORS ULTIMATE RESPONSIBILITY TO PROTECT THE BUILDING AND THE CONTENTS OF THE BUILDING FROM ALL RISKS RESULTING FROM THE WORK.** Contractor shall be sufficiently prepared to expediently install a temporary membrane to protect areas torn off or incomplete roofing in the event of precipitation.
- B. Repair any damage that results from the work of this Contract to Owner's satisfaction. Clean all floors, walls, walkways, and other surfaces from asphalt and other stains, and protect all paving, landscaping, and other site work from damage.
- C. Contractor shall build and maintain barriers as are necessary for the protection of person and property passing by the construction site. All barriers, etc. for this purpose shall comply will all federal, state, OSHA, and local ordinances.
- D. Contractor must take every precaution to prevent interior leakage, materials from falling into the interior, or other such occurrences. Installation of materials shall be accomplished in such a manner that material drippage does not occur.
- E. The Contractor shall prevent access by the public to materials, tools, equipment, or equipment. The Owner and the Consultant assume no liability or responsibility whatsoever for any damage, theft, or other acts that occur to the Contractor's material, tools, or equipment as a result of his negligence.
- F. Contractor's usage of the ground areas shall be designated by the Owner. Other than immediate necessary trucks and equipment, all vehicles shall be parked in legal, appropriate, designated parking areas off site.
- G. Coordinate all utility usage with the Owner. At no time shall utilities be wasted.
- H. Contractor will not be allowed to use the toilet facilities in the building. Contractor must provide portable toilets for their employees.
- I. Use of the Owner's telephones is prohibited, except for pay phones. Contractor shall provide his own telephone or use pay phones.
- J. Contractor shall be prepared to provide his own power as needed.

- K. Any electrical tools in use on the roof shall be protected by an OSHA approved Ground Fault Interrupter (GFI). All extension cords and electrical equipment shall be GFI grounded.
- L. Water needed for the execution of this contract will be furnished by the Owner. Contractor to supply all required hoses, pails, etc.
- M. During the progress of the work, promptly remove any spills onto the exposed finished surfaces and do not allow the accumulation of scrap and debris resulting from the work. Upon completion of the work, remove all excess materials from the job site. All clean up work shall be performed to the satisfaction of the Owner at the sole expense of the Contractor.
- N. Prior to final acceptance, the Contractor shall restore all areas affected by his work to their original state of cleanliness and repair all damage done to the premises, including the grounds, by his workmen and equipment.
- O. The Contractor shall be responsible for patching of existing asphalt shingle, slate roofing, and EPDM roofing not scheduled for replacement or alteration, which is damaged during any sequence of the work. The Contractor is also responsible for any water damage to existing insulation and building interior that may result from damage to the existing roofing, and or any subsequent water damage due to inadequate repair work.
- P. Existing materials designated to remain, which are damaged or defaced as a result of the work and are unsuitable for the use intended, shall be replaced at the Contractor's expense, to the satisfaction of the Owner.
- Q. Repairs of existing roofs required by the Contract, or necessary because of damage from this work, shall use products equivalent to, and compatible with, existing materials and applied only to clean and dry surfaces.

#### 1.29 REGULATIONS & SAFETY

- A. All work shall meet the requirements of all governing codes, ordinances, laws, regulations, safety orders, and directives relating to the work, including any specific requirements of the city and state of jurisdiction. This shall include the handling and disposal of any hazardous or potentially hazardous materials. The latest editions of standards and specifications listed herein shall apply to all procedures and materials used.
- B. Disturbing or disruptive noise that interferes with the normal building occupancy will not be permitted except when scheduled in advance with the Owner.
- C. The residents, building interiors, project site, and adjoining property must be protected from objectionable dust and wind-blown or falling debris.
- D. No accumulation of materials to be disposed will be permitted at any time. The Contractor is responsible for prompt removal from the site and disposal in a manner accepted by the local authorities. This shall include any required precautions or requirements related to disposal of hazardous or potentially hazardous materials.
- E. No means or methods shall be utilized in this contract that jeopardize safety to employees, the public, or to the property. Contractor shall hold harmless and defend Owner, Consultant, and their representatives for any violations, claims, or citations.

- F. Contractor shall strictly comply will all Federal, State, OSHA, and local regulations and requirements.
- G. Contractor shall provide for employee and public protection and be responsible for the erection, maintenance, supervision, and dismantling of such safety compliances.
- H. Contractor must obtain from the Town of Amherst all necessary permits, including building permit, sidewalk permit, street permit, parking permit, etc., before construction may commence.
- I. No torches, flame, or anything that can cause combustion shall be used where the possibility of combustion exists.
- J. Where torch use is required, precautionary measures shall be taken to minimize the risk of accidental combustion. One fully charged, certified, and operable fire extinguisher shall be within 20 feet of each torch being used on the roof. A minimum of two fire extinguishers must be on the roof at all times.
- K. Contractor's employees must wear shirts at all times and hard hats are required when work is being completed overhead.
- L. The presence of an Owner's representative or Consultant's representative is not to relieve the Contractor of his compliance with safety regulations. Neither the Owner nor the Consultant engage in the practice of safety engineering. It is the Contractor's responsibility to make certain that all of his employees, equipment, tools, etc. are in full compliance with local, state, federal, and OSHA requirements.

#### 1.29 CONTRACT CLOSE-OUT

- A. Surplus materials and all equipment shall be promptly removed from the site upon completion of the work. In case of undue delay or dispute, Owner may remove rubbish, materials, and equipment and charge cost to Contractor, with such action permissible by Owner 48 hours after a written notice has been transmitted to Contractor.
- B. Prior to final acceptance, Contractor shall restore all areas affected by his work to their original state of cleanliness and repair all damage done to the premises, including the grounds, by his workmen and equipment.

END OF SECTION

**DOCUMENT 00300****BID FORM**

To: Mr. Shawn Crawford  
 Whitney Management Corp.  
 9575 Katy Freeway, Suite 330  
 Houston, TX 77024

Project: St. Mary's Commons Apartments Roof Rehabilitation Project, 400 Mill Street, Williamsville, NY

Date: \_\_\_\_\_

Submitted by: \_\_\_\_\_

Address: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**1. OFFER**

Having examined the Place of the Work and all matters referred to in the Instructions to Bidders, Bid Documents, and Contract Documents prepared by THE BROWNE COMPANY ROOFING AND WATERPROOFING CONSULTANTS, INC., for the above referenced project, we the undersigned, hereby offer to enter into a Contract to perform the Work for the Contract Sum of:

**BASE BID No. 1 – New Roof System - Slate**

\_\_\_\_\_

(\$ \_\_\_\_\_) dollars, in lawful money of the United States of America.

(Contractor to include \$10,000 cash allowance and a quantity allowance of 2,000 sq. ft. of wood deck replacement (match existing construction) as per Section - 1.25 Allowances)

**BASE BID No. 2 – New Roof System – Synthetic Slate**

\_\_\_\_\_

(\$ \_\_\_\_\_) dollars, in lawful money of the United States of America.

(Contractor to include \$10,000 cash allowance and a quantity allowance of 2,000 sq. ft. of wood deck replacement (match existing construction) as per Section - 1.25 Allowances)

THE BROWNE COMPANY  
 Roofing and Waterproofing Consultants, Inc.

00300 - 1

St. Mary's Commons Apartments  
 Roof Rehabilitation Project

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**BASE BID No. 1 – New Roof System – Architectural Asphalt Shingles**

( \$ \_\_\_\_\_ ) dollars, in lawful money of the United States of America.

(Contractor to include \$10,000 cash allowance and a quantity allowance of 2,000 sq. ft. of wood deck replacement (match existing construction) as per Section - 1.25 Allowances)

**UNIT PRICES**

Unit Price No. 1 (Add) \$ \_\_\_\_\_ per sq. ft.

Price per square foot to replace the existing wood roof deck as directed by the Owner's representative.

Unit Price No. 2 (Add) \$ \_\_\_\_\_ per hour

Hourly labor rate for additional work, as directed by the Owner's representative, including all taxes, insurance, overhead, and profit.

**2. ACCEPTANCE**

This offer shall remain open to acceptance and shall be irrevocable for a period of thirty (30) calendar days from the bid closing date.

If the Owner accepts this bid within the time period stated above, we will:

- Execute the Agreement within seven days of receipt of acceptance of this bid.
- Furnish the required insurance certificates within seven days of receipt of acceptance of this bid in the form described in Supplementary Conditions.
- Commence work within seven days after written Notice to Proceed.

**3. CONTRACT TIME**

If this bid is accepted we will:

Complete the work in \_\_\_\_\_ calendar days from written Notice to Proceed, with  
work to begin on \_\_\_\_\_.

(The number of calendar days must be less than or equal to 60 calendar days, the Contract Time stipulated in Document 00100 - Instructions to Bidders, Section 1.05 - Contract Time.)

**4. ADDENDA**

The following Addenda have been received. The modifications to the Contract Documents noted therein have been considered and all costs thereto are included in the Bid Sum.

Addendum No. \_\_\_\_\_ Dated \_\_\_\_\_ Addendum No. \_\_\_\_\_ Dated \_\_\_\_\_

Addendum No. \_\_\_\_\_ Dated \_\_\_\_\_ Addendum No. \_\_\_\_\_ Dated \_\_\_\_\_

**5. BID FORM SIGNATURE(S)**

By signing this Bid Form, the Contractor acknowledges that they have read and understand the Project Contract Documents, and their obligations thereunder as they pertain to the work, that they have inspected the Project site and are familiar with the existing conditions that affect that work, and that they will comply with all of the requirements outlined in the Contract Documents.

Sign Bid Here: \_\_\_\_\_ Date: \_\_\_\_\_

Print Name & Title: \_\_\_\_\_

\_\_\_\_\_  
Legal Name of Person, Partnership, or Corporation

Legal Business Address: \_\_\_\_\_  
Street

\_\_\_\_\_  
City, State, and Zip

Phone No. \_\_\_\_\_ Fax No. \_\_\_\_\_

Email \_\_\_\_\_

**AFFIDAVIT REGARDING COLLUSION**

(If oath is taken outside of New York State, a County Clerk's Certificate as to the Authority of the officer administering the oath must be attached.)

EACH BIDDER IS REQUIRED TO EXECUTE THE FOLLOWING AFFIDAVIT:

STATE OF \_\_\_\_\_

COUNTY OF \_\_\_\_\_ SS:

CITY OF \_\_\_\_\_

\_\_\_\_\_ being duly sworn, deposes and says that

\_\_\_\_\_  
(If Individual, his address)

\_\_\_\_\_  
(If Partnership, names and address of Partners)

\_\_\_\_\_  
(If Corporation, names and titles of officers authorized to execute contracts)

By submission of this bid, each bidder and each person signing on behalf of any bidder certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best knowledge and belief:

1. The prices in this bid have been arrived at independently without collusion, consultation, communication, or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor.
2. Unless required by law, the prices which have been quoted in this bid have not been knowingly disclosed by the bidder and will not knowingly be disclosed by the bidder prior to opening, directly or indirectly, to any other bidder or to any competitor.
3. No attempt has been made or will be made by the bidder to induce any other person, partnership, or corporation to submit or not to submit a bid for the purpose of restricting competition.

\_\_\_\_\_  
Signature of Contractor

Sworn to before me this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

\_\_\_\_\_  
Signature of Notary Public/Commissioner of Deeds

THE BROWNE COMPANY  
*Roofing and Waterproofing Consultants, Inc.*

00300 - 4

St. Mary's Commons Apartments  
Roof Rehabilitation Project

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**SECTION 07300****SLATE SHINGLES & RELATED WORK (Base Bid No. 1)****PART 1 GENERAL****1.1 SECTION INCLUDES**

- A. Slate shingles, underlayment, eave, and ridge protection, metal flashings.

**1.2 RELATED SECTIONS**

- A. Section 06100 – Roof Related Wood Components

**1.3 REFERENCES**

- A. ASTM B 370 – Specification for Copper Sheet and Strip for Building Construction.
- B. ASTM C 406 – Specification for Roofing Slate.
- C. ASTM C 920 – Specification for Elastomeric Joint Sealants.
- D. ASTM D 1079 – Standard Terminology Relating to Roofing, Waterproofing, and Bituminous Materials.
- E. ASTM D 1970 – Specification for Self-Adhering Polymer Modified Bituminous Sheet Materials Used as Steep Roofing Underlayment for Ice Dam Protection.
- F. ASTM D 4869 – Specification for Asphalt-Saturated Organic Felt Underlayment Used in Steep Slope Roofing.
- G. ASTM D 7349 – Standard Test Method for Determining Capability of Roofing and Waterproofing Materials to Seal Around Fasteners.
- H. ASTM F1667 – Standard Specification for Driven Fasteners: Nails, Spikes and Staples
- I. North Country Slate – Slate Roofs: Design & Installation Manual – 2010 Edition – National Slate Association.
- J. NRCA – The NRCA Roofing and Waterproofing Manual. Definitions and Roofing Terminology.
- K. Sheet Metal & Air Conditioning Contractors National Association – Architectural Sheet Metal Manual.

#### 1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Details for specially configured metal flashing, jointing methods and locations for flashing, and other roofing system details.
- C. Selection Samples:
  - a. Pieces of actual slate shingles, illustrating complete range of colors available, for Architect's selection.
  - b. Pieces of actual metal ridge cap, 12 inches (300 mm) long and full width.
  - c. Actual snow guard, full size.
- D. Verification Samples:
  - a. Actual slate shingles in color selected, illustrating full range of color variation to be expected in finished work.
  - b. Underlayment 12 inches (300 mm) square.
- E. Material Test Reports: For each slate type, performed by a qualified testing laboratory as approved by North Country Slate, per ASTM C406.
- F. Certificate of Country of Origin: For each type of slate, identifying the country in which the slate shingles were quarried and fabricated.
- G. Distributor's Warranties: Distributors warranty for slate shingles specified.
- H. Installer's Warranties: Installers warranty for work specified.
- I. Installer's Qualifications: Installer's natural roofing slate project references; not fewer than four.
- J. Certificates of insurance for general liability and worker's compensation must be submitted to the Owner before work is started.

#### 1.5 QUALITY ASSURANCE

- A. Perform Work in accordance with NRCA (National Roofing Contractors Association) Steep Roofing Manual, Asphalt Roofing Manufacturer's guidelines, and slate shingle distributor's installation instructions.
- B. Installer Qualifications: Company experienced in installing natural slate roofing of the type and scope specified in this section and employing persons with not fewer than five years of documented experience. Company shall provide skilled workers, thoroughly trained and experienced in the necessary crafts of natural slate roof systems and who are familiar with this specification and methods required for a warrantable roof.
- C. Slate Shingle Distributors Warranty: Submit slate shingle distributors warranty, signed by the distributor and covering the slate shingles described in this section, in which the distributor agrees to replace slate shingles that fail in materials. The duration of this warranty shall be established by ASTM C406 and grade indicated in this specification.

- D. Roofing Installer's Warranty: Submit roofing installer's warranty, signed by roofing Installer and covering Work of this Section, in which roofing Installer agrees to repair or replace slate roofing that fails in materials or workmanship for 2 years from date of substantial completion.

#### 1.6 PRODUCT DELIVERY, STORAGE, & HANDLING

- A. All products delivered to the job site shall be in the original, unopened containers, with labels intact, legible, and bearing all seals and approvals.
- B. Handle all materials to prevent damage. The contractor shall take all precautions necessary so that loading, storage, and/or application of materials, and/or equipment does not overload the building structure.
- C. Deliver slate shingles to project site in distributor's crates/pallets, labeled with data indicating source.
- D. Handle shingles to prevent chipping, breakage, soiling, or other damage. Protect edges with wood or other rigid material.

#### 1.7 JOB CONDITIONS

- A. Do not apply roofing materials during inclement weather or to damp or frozen deck substrate.
- B. Only as much of the new roofing as can be made weather tight each day, including all flashing and detail work, shall be installed.
- C. All work shall be scheduled and executed without exposing the interior building areas to the effects of inclement weather. The existing building and its contents shall be protected against all risks.
- D. Arrange work sequence to avoid use of newly installed shingles as a walking surface or for equipment storage.
- E. Remove all dirt, dust, and debris from all surfaces to receive new materials.
- F. Site clean up of both interior and exterior building areas which have been affected by construction shall be completed to the Owner's satisfaction.
- G. Contractor shall not deviate from the manufacturer's printed application instructions.

#### 1.8 EXTRA MATERIALS

- A. Provide an additional 3 percent of installed field slates, but not less than one full crate/pallet, for Owners use in roof maintenance.

## PART 2 PRODUCTS

### 2.1 SLATE SHINGLE MANUFACTURER

- A. Subject to compliance with requirements, provides slate as furnished by North Country Slate, 880 Milner Ave. Unit B, Toronto, ON, Canada M1B 5N7.
- B. Substitutions permitted with written approval from the Consultant.

### 2.2 SLATE SHINGLES

- A. Slate Shingles: Hard, dense, sound rock, with chamfered edges, punched or drilled for two nails each. Slate shingles shall be punched or drilled back to front, and on the thinner end when there is variation in thickness along the length of the shingle.
- B. No slate shingles with broken corners shall be installed when either the base or leg of the right triangle piece broken off is greater than 1-1/2 inches (38 mm). No broken corners on covered ends which sacrifice nailing strength or laying a watertight roof. Broken corners are acceptable for cutting stock. Not more than 2 percent of broken slates, including those having cracks materially precluding ringing when sounded, shall be accepted.
- C. Slate shall be free of any visible inclusions of oxidizable iron pyrite.
- D. Curvature or twist in slate shingles shall not exceed 1/8 inch in 12 inches (3 mm in 100 mm). Curved slate shingles shall be trimmed and punched to permit them to be laid with convex side up. Knots, knurls and cramps are acceptable on the exposed slate shingle face. Knots, knurls and cramps on the back or covered portion of slate shingles, which prevent close contact of slate shingles or the laying of a watertight roof, will not be accepted.
- E. Slate shingles shall be trimmed with 90-degree square corners. Face dimensions of slate shingles shall not differ from those specified by more than 1/8 inch (3 mm).
  - a. Source: Obtain slate required for the project from a single quarry, with consistent color range, physical properties and texture throughout.
- F. Grade: ASTM C 406 Grade S1: Expected service life in excess of 75 years.
- G. Thickness: To match existing.
- H. Size: To match existing.
- I. Shape: To match existing.
- J. Starter Slate Size: Length of starter slates to be the exposure of the field slates plus the specified headlap and rounded up to the nearest full inch. Starter slates are to be front-side punched and installed chamfered edge down.
- K. Color: To match existing construction.

### 2.3 UNDERLAYMENT

- A. Eave (Ice Dam) Protection: W.R. Grace “Ice & Water Shield”, ASTM D1970, sheet barrier of self-adhering, rubberized asphalt bonded to sheet polyethylene, 58 mil total thickness, with strippable treated release paper. NO SUBSTITUTIONS PLEASE!

### 2.3 ACCESSORIES

- A. Slating Nails: Slater’s copper smooth shank nails, 0.120 inch (3 mm) or No. 11 gauge Stubs, not less than twice the nominal slate thickness plus 1 inch in length, with 3/8 inch (9 mm) head. Point should penetrate through underside of deck except where the underside of roof deck is exposed to view, where shorter nails are acceptable. Nails 1/2 inch (13 mm) or longer than field slate nails for slate hip and ridge installation.
- B. Butyl Rubber Sealant: ASTM C 1311, single-component, solvent-release; polyisobutylene plasticized; heavy bodied.
- C. Polymer Sealant: ASTM C 920 silicone sealant of type, grade, class, and use classification required to seal joints in slate-shingle roofing and remain watertight.
- D. Roof Decking: Equal to Georgia Pacific, Blue Ribbon, 7/16” Exterior Grade OSB Roof Sheathing

### 2.4 FLASHING MATERIALS

- A. Flashing: ASTM B 370 copper, cold rolled, 16 oz/sq ft (0.56 mm thick), natural finish.
- B. Gutter Lining: ASTM B 370 copper, cold rolled, 20 oz/sq ft (0.69 mm thick), natural finish.

### 2.5 FLASHING FABRICATION

- A. Form flashings (to profiles indicated on Drawings, and) to protect roofing materials from physical damage and to shed water.
- B. Form sections square and accurate to profile, in maximum possible lengths, free from distortion or defects detrimental to appearance or performance.
- C. Hem exposed edges of flashings minimum ¼” on underside.
- D. Apply bituminous paint on concealed surfaces of flashings.

## PART 3 EXECUTION

### 3.1 EXAMINATION AND PREPARATION

- A. Completely remove existing slate shingles down to the structural wood deck. (Note: Contractor must provide their own dumpsters.)
- B. Remove the existing siding as required to allow for the installation of new wall flashing and new metal step flashings.
- B. Verify that plumbing stacks and roof penetrations are flashed to deck surface.
- C. Verify deck surfaces are dry, free of ridges, warps, or voids. Broom clean surfaces.
- D. Fill knot holes and surface cracks with latex filler at areas of bonded eave protection.
- E. Remove existing gutter lining.
- G. All roof deck and wall replacement to be as per the pre-determined square foot price.

### 3.2 INSTALLATION – NEW OSB DECKING

- A. Install new 7/16” OSB panels in the long direction, spacing the panels 1/8” on all sides and staggering the joints of upper rows of panels.
- B. Textured side of new OSB panels should be facing up and join ends’ of panels over framing members.
- C. Secure new OSB panels using 8D common nails installed 6” o.c. at the perimeter of panels and 12” o.c. in the field of the panels.
- D. Install “H-Clips at panel edges between adjacent panels and between framing members.

### 3.3 INSTALLATION – EAVE ICE DAM PROTECTION

- A. Place eave [and gable] edge metal flashings tight with fascia boards. Weather lap joints and seal with plastic cement. Secure flange with nails.
- B. Apply rubberized asphalt/polyethylene sheet ice dam protection membrane, in accordance with manufacturer's instructions, where called for on the Contract Drawings.

### 3.4 INSTALLATION - VALLEY PROTECTION

- A. Center first row of ice and water shield membrane (36") over the valleys. Install two more rows (68") on each side of the valley.
- B. Place one ply of roll roofing, over ice dam membrane, centered over valleys. [Place with mineral surfaced side down.] Weather lap joints and nail in place.
- C. Install new copper valley flashings on hidden cleats as per the Contract Drawings.

### 3.5 INSTALLATION - METAL FLASHINGS

- A. Install metal drip edge at all eaves and rakes. Weather lap joints and seal weather tight with plastic cement. Secure in place with concealed fastenings.
- B. Flash and seal work projecting through or mounted on roofing with plastic cement, weather tight.
- C. Where siding has been removed, install ice and water shield up the wall and down on to the roof surface.
- D. Interweave new copper step flashings with the new shingles where the roofs' intersect with the higher walls. Re-install the existing wood siding or install new wood siding to match the existing construction.
- D. Where the chimneys intersect with the shingle roofs, install new copper counterflashings and apron flashing as required.

### 3.6 INSTALLATION – SLATE SHINGLES

- A. Install shingles in accordance with manufacturer's printed instructions.
- B. Sweep the surface clean of all debris. Since any irregularities may show through the new shingles, be sure the underlying substrate provides a smooth surface.
- C. Slate Grading: Do not sort slates according to thickness. Install slates randomly selected, beginning at the eaves and progressing up the roof slope, creating a textured overall appearance. Slate thickness variations preventing the laying of a weather tight roof will not to be permitted. Blend slates from all crates/pallets together to achieve a uniform color and texture to the roof.
- D. Install starter course of slate shingles, as per the Manufacturer's application instructions.
- E. Install shingles as per the manufacturer's application instructions. Make certain that shingle exposures and nail locations are as instructed.
- F. Install slate shingles to match existing slate layout.
- G. Extend shingles ½" beyond face of rake edge fascia boards.
- H. Interweave step flashings with new shingles at all walls.
- I. Joint Spacing: Slate shingles in each course to be installed with no joint spacing (butted

together).

- J. Cut and fit shingles neatly around vents, pipes, ventilators, and other roof projections.
- K. Slate shingles overlapping sheet metal shall have nails placed so as to avoid penetrating the sheet metal.
- L. Nail slate shingles so nail heads touch shingle lightly, without producing strain on the slate.
- M. Complete installation to provide weather tight service.

### 3.7 BUILT-IN GUTTER & DOWNSPOUT WORK

- A. Install new copper lining, over new ice and water shield membrane, at existing built-in gutters, and new downspouts upon completion of roofing work.
- B. Connect new downspouts to the existing storm drains.

END OF SECTION

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

## SECTION 07310

### SYNTHETIC SLATE SHINGLES & RELATED WORK (Base Bid No. 2)

#### PART 1 GENERAL

##### 1.1 SECTION INCLUDES

- A. Synthetic slate shingles, underlayment, eave, and ridge protection, metal flashings.

##### 1.2 SUBMITTALS

- A. Product Data: Provide data indicating material characteristics, limitations, and installation instructions.
- B. Shop drawings illustrating synthetic shingle layout, flashings, conditions at built-in gutters, hips, ridges, and rakes.
- C. Samples: Submit to the Owner a sample of all materials to be used on this project
- D. Sample copies of contractor's warranty and shingle manufacturer's warranty.
- E. Certificates of insurance for general liability and worker's compensation must be submitted to the Owner before work is started.

##### 1.3 QUALITY ASSURANCE

- A. Perform Work in accordance with NRCA (National Roofing Contractors Association) Steep Roofing Manual, Asphalt Roofing Manufacturer's guidelines, and shingle manufacturer's installation instructions.
- B. Shingles to have a UL Class "A" Fire Hazard Classification and a UL wind rating of up to 100 mph.
- C. Shingles to have a 50-year, transferable, manufacturer's warranty.
- D. New shingles shall only be applied by a manufacturer-approved contractor.
- E. Contractor to supply a five-year watertight warranty.

##### 1.4 PRODUCT DELIVERY, STORAGE, & HANDLING

- A. All products delivered to the job site shall be in the original, unopened containers, with labels intact, legible, and bearing all seals and approvals.
- B. Handle all materials to prevent damage. The contractor shall take all precautions necessary so that loading, storage, and/or application of materials, and/or equipment does not overload the building structure.

THE BROWNE COMPANY  
Roofing and Waterproofing Consultants, Inc.

07310 - 1

St. Mary's Commons Apartments  
Roof Rehabilitation Project

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

## 1.5 JOB CONDITIONS

- A. Do not apply roofing materials during inclement weather or to damp or frozen deck substrate.
- B. Only as much of the new roofing as can be made weather tight each day, including all flashing and detail work, shall be installed.
- C. All work shall be scheduled and executed without exposing the interior building areas to the effects of inclement weather. The existing building and its contents shall be protected against all risks.
- D. Arrange work sequence to avoid use of newly installed shingles as a walking surface or for equipment storage.
- E. Remove all dirt, dust, and debris from all surfaces to receive new materials.
- F. Site clean up of both interior and exterior building areas which have been affected by construction shall be completed to the Owner's satisfaction.
- G. Contractor shall not deviate from the manufacturer's printed application instructions.
- H. Follow synthetic shingle manufacturer's specific installation instructions, when the outside temperature falls below 40°F, and when the roof slope is 4/12 (as this roof is.)

## PART 2 PRODUCTS

### 2.1 ASPHALT SHINGLES

- A. Manufacturer: EcoStar LLC or DaVinci Roofscapes, LLC.
  - 1. Shingle: 50-year, synthetic type shingle, color to be selected by Owner.
  - 2. Synthetic Shingles: UL Rating of "A" and Wind Resistance Label.
  - 3. Installed Weight (6" exposure): 342 lbs. per square.
  - 4. Size: 18" long with varying widths.

THE BROWNE COMPANY  
Roofing and Waterproofing Consultants, Inc.

07310 - 2

St. Mary's Commons Apartments  
Roof Rehabilitation Project

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

## 2.2 SHEET MATERIALS

- A. Roll Roofing: Asphalt saturated roll roofing; surfaced on weather side with mineral granules of the same color and manufacturer as the new asphalt shingles.
- B. Eave (Ice Dam) Protection: W.R. Grace “Ice & Water Shield”, ASTM D1970, sheet barrier of self-adhering, rubberized asphalt bonded to sheet polyethylene, 58 mil total thickness, with strippable treated release paper. NO SUBSTITUTIONS PLEASE!
- C. Underlayment: Titanium UDL Synthetic Roofing Underlayment.

## 2.3 ACCESSORIES

- A. Nails: Copper 3/8” inch flat head roofing nails, 1-1/2” long.
- B. Roof Decking: Equal to Georgia Pacific, Blue Ribbon, 7/16” Exterior Grade OSB Roof Sheathing

## 2.4 FLASHING MATERIALS

- A. Flashing: ASTM B 370 copper, cold rolled, 16 oz/sq ft (0.56 mm thick), natural finish.
- B. Gutter Lining: ASTM B 370 copper, cold rolled, 20 oz/sq ft (0.69 mm thick), natural finish
- C. Counterflashing and step flashings: 16 oz. copper.
- D. Bituminous Paint: Acid and alkali resistant type; black color.

## 2.5 FLASHING FABRICATION

- A. Form flashings (to profiles indicated on Drawings, and) to protect roofing materials from physical damage and to shed water.
- B. Form sections square and accurate to profile, in maximum possible lengths, free from distortion or defects detrimental to appearance or performance.
- C. Hem exposed edges of flashings minimum 1/4” on underside.
- D. Apply bituminous paint on concealed surfaces of flashings.

## PART 3 EXECUTION

### 3.1 EXAMINATION AND PREPARATION

- A. Completely remove existing slate shingles down to the structural wood deck (Note: Contractor must provide their own dumpsters.)
- B. Remove the existing siding as required to allow for the installation of new wall flashing and new metal step flashings.
- D. Verify that plumbing stacks and roof penetrations are flashed to deck surface.
- E. Verify deck surfaces are dry, free of ridges, warps, or voids. Broom clean surfaces.
- E. Fill knot holes and surface cracks with latex filler at areas of bonded eave protection.
- F. All roof deck/wall replacement to be as per the pre-determined square foot price.

### 3.2 INSTALLATION – NEW OSB DECKING

- A. Install new 7/16" OSB panels in the long direction, spacing the panels 1/8" on all sides and staggering the joints of upper rows of panels.
- B. Textured side of new OSB panels should be facing up and join ends' of panels over framing members.
- C. Secure new OSB panels using 8D common nails installed 6" o.c. at the perimeter of panels and 12" o.c. in the field of the panels.
- D. Install "H-Clips at panel edges between adjacent panels and between framing members

### 3.3 INSTALLATION – EAVE ICE DAM PROTECTION

- A. Place eave [and gable] edge metal flashings tight with fascia boards. Weather lap joints and seal with plastic cement. Secure flange with nails.
- B. Apply rubberized asphalt/polyethylene sheet ice dam protection membrane, in accordance with manufacturer's instructions, where called for on the Contract Drawings.

### 3.4 INSTALLATION - VALLEY PROTECTION

- A. Center first row of ice and water shield membrane (36") over the valleys. Install two mor rows (68") on each side of the valley.
- B. Place one ply of roll roofing, over ice dam membrane, centered over valleys. [Place with mineral surfaced side down.] Weather lap joints and nail in place.
- C. Install new copper valley flashings on hidden cleats as per the Contract Drawings.

### 3.4 INSTALLATION - METAL FLASHINGS

- A. Install metal drip edge at all eaves and rakes. Weather lap joints and seal weather tight with plastic cement. Secure in place with concealed fastenings.
- B. Flash and seal work projecting through or mounted on roofing with plastic cement, weather tight.
- C. Where siding has been removed, install ice and water shield up the wall and down on to the roof surface.
- D. Interweave new copper step flashings with the new shingles where the roofs' intersect with the higher walls. Re-install the existing wood siding or install new wood siding to match the existing construction.
- E. Where the chimneys intersect with the shingle roofs, install new copper counterflashings and apron flashing as required.

### 3.5 INSTALLATION – SYNTHETIC SHINGLES

- A. Install shingles in accordance with manufacturer's printed instructions.
- B. Sweep the surface clean of all debris. Since any irregularities may show through the new shingles, be sure the underlying substrate provides a smooth surface.
- C. Install rake edge metal to match existing rake edges.
- D. Install starter course of shingles, as per the Manufacturer's application instructions.
- E. Install shingles as per the manufacturer's application instructions. Make certain that shingle exposures and nail locations are as instructed.
- F. Install shingles to match existing slate layout.
- G. Extend shingles ½" beyond face of rake edge fascia boards.
- H. Interweave step flashings with new shingles at all walls.
- I. Complete installation to provide weather tight service.

### 3.6 BUILT-IN GUTTER & DOWNSPOUT WORK

- C. Install new copper lining, over new ice and water shield membrane, at existing built-in gutters, and new downspouts upon completion of roofing work.
- D. Connect new downspouts to the existing storm drains.

END OF SECTION

THE BROWNE COMPANY  
Roofing and Waterproofing Consultants, Inc.

07310 - 5

St. Mary's Commons Apartments  
Roof Rehabilitation Project

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**SECTION 07311****ARCHETECTURAL ASPHALT SHINGLES & RELATED WORK (Base Bid No. 3)****PART 1 GENERAL****1.1 SECTION INCLUDES**

- E. Granular surfaced asphalt shingle roofing, underlayment, eave, and ridge protection, metal flashings.

**1.2 SUBMITTALS**

- A. Product Data: Provide data indicating material characteristics, and limitations.
- B. Samples: Submit to the Owner a sample of all materials to be used on this project.
- C. Sample copies of contractor's warranty and shingle manufacturer's warranty.
- D. Certificates of insurance for general liability and worker's compensation must be submitted to the Owner before work is started.

**1.3 QUALITY ASSURANCE**

- A. Perform Work in accordance with NRCA (National Roofing Contractors Association) Steep Roofing Manual, Asphalt Roofing Manufacturer's guidelines, and shingle manufacturer's installation instructions.
- B. Shingles to have a UL Class "A" Fire Hazard Classification and a UL wind rating of up to 110 mph.
- C. Shingles to have a 40-year, transferable, manufacturer's warranty.
- D. New shingles shall only be applied by a manufacturer-approved contractor.
- E. Contractor to supply a five-year watertight warranty.

**1.4 PRODUCT DELIVERY, STORAGE, & HANDLING**

- A. All products delivered to the job site shall be in the original, unopened containers, with labels intact, legible, and bearing all seals and approvals.
- B. Handle all materials to prevent damage. The contractor shall take all precautions necessary so that loading, storage, and/or application of materials, and/or equipment does not overload the building structure.

## 1.5 JOB CONDITIONS

- A. Do not apply roofing materials during inclement weather or to damp or frozen deck substrate.
- B. Only as much of the new roofing as can be made weather tight each day, including all flashing and detail work, shall be installed.
- C. All work shall be scheduled and executed without exposing the interior building areas to the effects of inclement weather. The existing building and its contents shall be protected against all risks.
- D. Arrange work sequence to avoid use of newly installed shingles as a walking surface or for equipment storage.
- E. Remove all dirt, dust, and debris from all surfaces to receive new materials.
- F. Site clean up of both interior and exterior building areas which have been affected by construction shall be completed to the Owner's satisfaction.
- G. Contractor shall not deviate from the manufacturer's printed application instructions.
- H. Follow shingle manufacturer's specific installation instructions, when the outside temperature falls below 40°F, and when the roof slope is 4/12 (as this roof is.)

## 1.6 WARRANTIES

- A. Lifetime, limited transferable warranty from the roofing system manufacturer
- B. 10-year roofing system manufacturer's warranty (100% replacement and labor costs due to manufacturing defects)
- C. 15-year roofing system manufacturer's warranty against streaking and discoloration caused by airborne algae
- D. 15-year, 110-mph wind-resistance warranty
- E. 2-year contractor guarantee.

## PART 2 PRODUCTS

### 2.1 ASPHALT SHINGLES

A. Manufacturer: Certainteed, or GAF.

1. Shingle: Lifetime, architectural type shingle, color to be selected by Owner.
2. Asphalt Shingles: ASTM D3462, Class A, Type I - Self Sealing; UL Rating of "A" and Wind Resistance Label, glass fiber mat base, mineral granule surface type; self sealing type.

B. Shingle to be either Certainteed Grand Manor or GAF Camelot II.

### 2.2 SHEET MATERIALS

- A. Roll Roofing: Asphalt saturated roll roofing; surfaced on weather side with mineral granules of the same color and manufacturer as the new asphalt shingles.
- B. Eave (Ice Dam) Protection: W.R. Grace "Ice & Water Shield", ASTM D1970, sheet barrier of self-adhering, rubberized asphalt bonded to sheet polyethylene, 58 mil total thickness, with strippable treated release paper. NO SUBSTITUTIONS PLEASE!
- C. Underlayment: Equal to Titanium UDL Synthetic Roofing Underlayment.

### 2.3 ACCESSORIES

- A. Nails: Hot dipped zinc coated steel, 11-12 gauge, barbed or deformed shank roofing nails with heads 3/8" to 7/16" in diameter, of sufficient length to penetrate roof sheathing.
- B. Plastic Cement: Karnak, ASTM D4586, Type II, asbestos free, asphalt type with mineral fiber components.
- C. Asphalt Primer: Equal to Karnak #100 Asbestos Free, Non-Fibered, Quick Drying Primer.
- D. Fascia & Rake Board: Clear pine 1" x desired width.
- E. Roof Decking: Equal to Georgia Pacific, Blue Ribbon, 7/16" Exterior Grade OSB Roof Sheathing
- F. Roof Deck Panel Edge Clips ("H" Clips): Equal to TECO galvanized steel H-Clip

## 2.4 FLASHING MATERIALS

- A. New Roof Edge Flashing: 20 oz. cold rolled copper.
- B. New Valley Flashing: 20 oz. cold rolled copper.
- C. Counterflashing and step flashings: 20 oz. cold rolled copper.
- D. Bituminous Paint: Acid and alkali resistant type; black color.
- E. Vent Pipe Flashing: Manufacturer approved, pre-fabricated pipe flashings
- F. Gutters, Downspouts, and Trim Metal: 20 oz. cold rolled copper. Gutters to be a 6" gutter system and downspouts to be 3" x 4".

## 2.5 FLASHING FABRICATION

- A. Form flashings (to profiles indicated on Drawings, and) to protect roofing materials from physical damage and to shed water.
- B. Form sections square and accurate to profile, in maximum possible lengths, free from distortion or defects detrimental to appearance or performance.
- C. Hem exposed edges of flashings minimum 1/4" on underside.
- D. Apply bituminous paint on concealed surfaces of flashings.

## PART 3 EXECUTION

### 3.1 EXAMINATION AND PREPARATION

- A. Completely remove existing roofing down to the structural wood deck where called for on the Contract Drawings. (Note: Contractor must provide their own dumpsters.)
- B. Remove the existing flashings.
- C. Verify that plumbing stacks and roof penetrations are flashed to deck surface.
- D. Verify deck surfaces are dry, free of ridges, warps, or voids. Broom clean surfaces.
- E. Fill knot holes and surface cracks with latex filler at areas of bonded eave protection.
- F. Remove all existing gutters and downspouts.
- C. All roof deck replacement to be as per the Contract Drawings and the pre-determined unit price.

### 3.2 INSTALLATION – NEW OSB DECKING

- A. Install new 7/16" OSB panels in the long direction, spacing the panels 1/8" on all sides and staggering the joints of upper rows of panels.
- B. Textured side of new OSB panels should be facing up and join ends' of panels over framing members.
- C. Secure new OSB panels using 8D common nails installed 6" o.c. at the perimeter of panels and 12" o.c. in the field of the panels.
- D. Install "H-Clips at panel edges between adjacent panels and between framing members.

### 3.3 INSTALLATION – EAVE ICE DAM PROTECTION

- A. Place eave [and gable] edge metal flashings tight with fascia boards. Weather lap joints and seal with plastic cement. Secure flange with nails.
- B. Apply rubberized asphalt/polyethylene sheet ice dam protection membrane, in accordance with manufacturer's instructions, where called for on the Contract Drawings.

### 3.4 INSTALLATION - VALLEY PROTECTION

- D. Center first row of ice and water shield membrane (36") over the valleys. Install two more rows (68") on each side of the valley.
- E. Place one ply of roll roofing, over ice dam membrane, centered over valleys. [Place with mineral surfaced side down.] Weather lap joints and nail in place.

### 3.5 INSTALLATION - METAL FLASHINGS

- A. Install metal drip edge at all eaves and rakes. Weather lap joints and seal weather tight with plastic cement. Secure in place with concealed fastenings.
- B. Flash and seal work projecting through or mounted on roofing with plastic cement, weather tight.
- C. Install ice and water shield up the wall and down on to the roof surface.
- D. Interweave new copper step flashings with the new shingles where the roofs' intersect with the higher walls.
- E. Where the chimneys intersect with the shingle roofs, install copper counterflashings and apron flashing as required.

### 3.6 INSTALLATION - ASPHALT SHINGLES

- A. Install shingles in accordance with manufacturer's printed instructions (on each bundle).
- B. Sweep the surface clean of all debris. Since any irregularities may show through the new shingles, be sure the underlying shingles provide a smooth surface.
- C. Install rake edge metal to match existing rake edges.
- D. Install starter course of shingles, making certain that self-sealing adhesive is at the outside edge.
- E. Install shingles as per the manufacturer's application instructions. Make certain that shingle exposures and nail locations are as instructed.
- F. Extend shingles ½" beyond face of rake edge fascia boards.
- G. Interweave step flashings with new shingles at all walls.
- H. Complete installation to provide weather tight service.

### 3.7 VALLEY FLASHING INSTALLATION

- A. Open Valley: Install new minimum 18" wide, 20 oz. copper flashing over new valley protection (ice and water shield membrane and roll roofing.).
- B. Hem flanges of new copper valley metal and secure with hidden cleats, 12" o.c.
- C. Seal underneath ends' of shingles covering the outer edges of the new valley metal.

END OF SECTION

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)

**SECTION 07460**  
**FIBER CEMENT SIDING**

**PART 1 GENERAL**

**1.1 SECTION INCLUDES**

- A. Siding of the following types:
  - 1. Fiber Cement Siding

**1.2 RELATED SECTIONS**

- A. Section 07620 – Sheet Metal Flashing & Trim.

**1.3 SUBMITTALS**

- A. Product Data: Provide data indicating material characteristics, limitations, and installation instructions.
- B. Shop drawings illustrating synthetic shingle layout, flashings, conditions at built-in gutters, hips, ridges, and rakes.
- C. Samples: Submit to the Owner a sample of all materials to be used on this project.
- D. Sample copies of contractor's warranty and siding manufacturer's warranty.
- E. Verification Samples: For each finish product specified, two samples, representing actual product and color.

**1.4 QUALITY ASSURANCE**

- A. Installer Qualifications: Installer shall be licensed, registered or otherwise acceptable to authorities having jurisdiction to install exterior building products.

**1.5 DELIVERY, STORAGE, AND HANDLING**

- A. Inspect the materials upon delivery to assure specified products have been received. Store products in a safe area, away from construction traffic. Store under cover and off the ground, protected from moisture.

**1.6 PROJECT CONDITIONS**

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's recommended limits.

## 1.7 WARRANTY

- A. Material Warranty: Provide manufacturer's standard warranty and as follows:
  - 1. 50 year warranty against rot, delamination and excessive swelling for installation.
- B. Coating Warranty: Provide manufacturer's standard warranty and as follows:
  - 1. Coatings: 15 year warranty on the coating when factory applied.

## PART 2 PRODUCTS

### 2.1 MANUFACTURERS

- A. Acceptable Manufacturer: James Hardie Building Products, Inc.
- B. Acceptable Manufacturer: Woodtone, which is located at: 8007 Aitken Rd.; Chilliwack, BC, Canada V2R 4H5.
  - 1. Type: Horizontal Siding..
    - a. Equal to Hardie Shingle Siding Individual Shingle.
  - 2. Finish: Factory applied finish, color to be selected by Owner.
- C. Nails for Fiber Cement Wood Siding:
  - 1. 0.091" x 0.221 x 1-1/2" or 0.121 x 0.37" HD x 1-1/4" long corrosion resistant siding nails.

## PART 3 EXECUTION

### 3.1 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

### 3.2 INSTALLATION

- A. Install in accordance with manufacturer's instructions including the following:
  - 1. Coordinate work with related trades; scribe and cope siding boards for accurate fit. Allow for installation of related work to avoid cutting and patching.
  - 2. Select siding boards of longest practical lengths. Discard boards that are warped, twisted, bowed, crooked or otherwise defective.
  - 3. Comply with siding manufacturer's and substrate manufacturer's installation instructions. Comply with local building codes and regulations.
  - 4. Apply touch up coating on surfaces and ends cut during installation.
  - 5. As work proceeds, maintain premises free of unnecessary accumulation of tools, equipment, surplus materials, and debris related to this work.
- B. Finish materials on all ends and sides and ends. Apply touch up coating on new cuts. Factory finishing is preferred.

### 3.3 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

**SECTION 07530****FULLY ADHERED EPDM ROOFING SYSTEM****PART 1 GENERAL****1.01 SECTION INCLUDES**

- A. Provide all labor, equipment, and materials to remove existing EPDM roof system and install new fully adhered EPDM roof system.

**1.02 SYSTEM DESCRIPTION**

- A. Elastomeric Sheet Roofing System: Elastomeric sheet membrane roofing system fully adhered over new overlayment board and new roof insulation, on existing roof deck.
- B. NRCA Specification Plate: 46-3 IESF
- C. Related Work: The Work includes but is not necessarily limited to the installation of:
  - 1. Sheet metal flashings
- D. Upon successful completion of the Work the following warranties will be obtained:
  - 1. Roofing Contractor (Applicator) Warranty
  - 2. Manufacturer's Warranty

**1.03 QUALITY ASSURANCE**

- A. Perform Work in accordance with NRCA Roofing and Waterproofing Manual and Manufacturer's printed instructions.
- B. UL: Class A Fire Hazard Classification.
- C. FM: Roof Assembly Classification, wind uplift requirement of I90, in accordance with FM Construction Bulletin 1-28.
- D. Only a Contractor authorized by the Manufacturer prior to bid shall apply the roofing system.

**1.04 SUBMITTALS**

- A. Prior to the start of any roofing work, the Contractor shall submit the following to the Owner's representative:
  - 1. A list of materials intended for use on this project.
  - 2. Copies of Manufacturer's specifications and current product literature.
  - 3. Samples of each component to be used in the roof system.
  - 4. Sample copy of Contractor's Warranty.
  - 5. Sample copy of Manufacturer's Warranty.
  - 6. Certification that the Contractor is an approved Applicator of the system intended for use.

7. Certification by the Manufacturer that all materials supplied comply with all requirements of the identified ASTM and industry standards or practices.
8. Technical acceptance by the Manufacturer of Contract Specifications and Drawings.
9. Certification from the Manufacturer that the system specified meets all identified code and insurance requirements.
10. Certification from the Manufacturer that all products used for the installation of the new roofing system are to be completely asbestos free.

#### 1.05 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. All products delivered to the job site shall be in the original unopened containers with labels intact, legible, and bearing all seals and approvals.
- B. Handle all materials to prevent damage. Store roofing materials on raised platforms and cover with suitable waterproof coverings.
- C. All materials, which are deemed to be damaged by the Owner's representative, are to be removed from the job site and replaced at no cost to the Owner.

#### 1.06 JOB CONDITIONS

- A. Do not apply roofing membrane during inclement weather or to damp or frozen deck substrate.
- B. Only as much of the new roofing as can be made weather tight each day, including all flashing and detail work, shall be installed.
- C. All work shall be scheduled and executed without exposing the interior building areas to the effects of inclement weather. The existing building and its contents shall be protected against all risks.
- D. Uninterrupted water stops shall be installed at the end of each day's work and shall be completely removed before proceeding with the next day's work.
- E. Arrange work sequence to avoid use of newly constructed roofing as a walking surface or for equipment moving and storage. Where such access is absolutely required, the Contractor shall provide the necessary protection to prevent damage to the new roofing.
- F. Remove all dirt, dust, and debris from all surfaces to receive new materials.
- G. The Contractor shall take precautions that storage and/or application of materials and/or equipment does not overload the roof deck or building structure.
- H. The Contractor shall verify that all roof drain lines are functioning properly before starting work. Contractor shall report any blockages in writing to the Owner's representative for corrective action prior to installation of the new roofing system.
- I. Contractor shall immediately stop work if any unusual or concealed condition is discovered that will preclude installation of the roof system as specified. Contractor shall make sure roof is weather tight and notify Owner in writing of such condition.

- J. Site clean up of both interior and exterior building areas, which have been affected by construction, shall be completed to the Owner's satisfaction.
- K. The Contractor shall arrange to have fastener pullout tests conducted in accordance with industry standards to help verify condition of deck/substrate and to confirm expected pullout values.
- L. Keep all primers, fuels, adhesives, sealants, and cleaning materials away from all ignition sources (i.e. torches, flames, sparks, etc.)
- M. Consult container labels and Material Safety Data Sheets for specific safety requirements.
- N. When outside temperature falls below 50 F, the fully adhered system may require additional precautions.
- O. Fumes from adhesive solvents may be drawn into the building during installation through rooftop intakes. Appropriate measures must be taken to assure that fumes from adhesive solvents are not drawn into the building through air intakes.

#### 1.07 WARRANTIES

- A. Provide Contractors two (2) year watertight warranty.
- B. Provide Manufacturer's twenty (20) year no dollar limit, system warranty with wind speed attachment to cover wind speeds up to and including 90 mph (regardless of building height) as measured at the National Weather Service Office at Greater Buffalo International Airport.

## PART 2 PRODUCTS

### 2.01 GENERAL

- A. All components of the proposed roof system must be supplied by a single Manufacturer and included in their Warranty. Different Manufacturers may be used as long as their products are approved for use and included in the membrane Manufacturer's Warranty.

### 2.02 ACCEPTABLE MANUFACTURERS AND SYSTEMS

- A. Carlisle Fully Adhered EPDM
- B. Elevate Fully Adhered EPDM
- C. Johns-Manville Fully Adhered EPDM

### 2.03 ELASTOMERIC SHEET ROOFING MATERIALS

- A. EPDM Membrane: .090 FR EPDM
- B. EPDM Flashing: .090 FR EPDM and uncured .060 EPDM at corners.
- C. Reinforced Perimeter Securement Strip: 6" wide reinforced EPDM.
- D. Bonding Adhesive: As recommended by the manufacturer.
- E. Splice Adhesive: As recommend by the manufacturer.
- F. Miscellaneous EPDM Accessories: As recommended by the manufacturer.

### 2.04 ROOF OVERLAYMENT

- A. Overlayment: Equal to 5/8" Securock Gypsum Fiber Roof Board.
- B. Mechanical Attachment:
  - 1. Overlayment shall be mechanically attached (minimum of 1 fastener per 2 square feet) to the deck with fasteners and plates approved by Factory Mutual and the Manufacturer to meet their wind speed warranty requirements. (Note: Overlayment and attachment of overlayment must be covered under the membrane Manufacturer's warranty.)
  - 2. The quantity and location of the insulation fasteners shall also cause the roof overlayment boards to rest evenly on the roof deck/substrate so that there are no large cavities or air spaces between the boards and the substrate.
  - 3. **Pull-out tests must be performed and results submitted to the Owner's representative before any underlayment or roof insulation boards may be installed.**

4. Overlayment and attachment of overlayment must be covered under the membrane manufacturer's warranty.

## 2.05 ACCESSORY PRODUCTS

- A. Roof Decking: Equal to Georgia Pacific, Blue Ribbon, 7/16" Exterior Grade OSB Roof Sheathing.
- B. Treated Wood Blocking: Treated wood blocking shall be fire and rot resistant, #2 or better wolmanized or osmose treated. Creosote or asphaltic treated lumber is unacceptable.
- C. Roof Drain Inserts: See Section 07620 – Sheet Metal Flashing and Trim.

## PART III EXECUTION

### 3.01 GENERAL

- A. The Contractor shall coordinate the installation so that each area is made watertight at the end of each work day.

### 3.02 SUBSTRATE PREPARATION

- A. The substrate must be structurally sound and suitable to accept the new roofing system. Fastener pullout tests must be performed to verify deck condition and adequate fastener pullout resistance.
- B. The substrate must be free of all debris, sharp edges, and other irregularities.
- C. The substrate must be dry and free of snow or ice.
- D. Preparation of existing roofing:
  1. Remove existing EPDM membrane and underlayment board.
  2. Remove all existing perimeter, wall, and roof flashings. Remove only that amount of flashing that can be made weather tight with new materials during a one-day period or onset of inclement weather.
  3. All lead jacks, sleeves, and flashings shall be removed from vent pipes, stacks, roof drains, etc.
- A. Remove existing roof drain clamping rings, strainers, sleeves, etc., and clean/prepare for re-use.

### 3.03 INSTALLATION – NEW OSB DECKING

- A. Install new 7/16" OSB panels in the long direction, spacing the panels 1/8" on all sides and staggering the joints of upper rows of panels.
- B. Textured side of new OSB panels should be facing up and join ends' of panels over framing members.
- C. Secure new OSB panels using 8D common nails installed 6" o.c. at the perimeter of panels and 12" o.c. in the field of the panels.
- D. Install "H-Clips at panel edges between adjacent panels and between framing members.

### 3.04 OVERLAYMENT INSTALLATION

- A. Overlayment shall be neatly cut to fit snugly around penetrations and projections.
- B. All end joints shall be staggered and joints of top layer of insulation shall be offset a minimum of 6" over the joints of the bottom layer. No gaps greater than 1/4" will be permitted.
- C. Overlayment board shall be mechanically attached (minimum of 1 fastener per 2 square feet) to the deck with fasteners and plates approved by Factory Mutual and the Manufacturer to meet their wind speed warranty requirements. (Note: Overlayment and attachment of Overlayment must be covered under the membrane Manufacturer's warranty.)

### 3.05 MEMBRANE APPLICATION

- A. Install reinforced perimeter flashing strip with manufacturer's approved fasteners and plates at the perimeter of all walls, expansion joints, and curbs.
- B. Place membrane panel, without stretching, over the acceptable substrate and allow to relax for a minimum of 30 minutes before applying bonding adhesive.
- C. Apply bonding adhesive to the underlayment substrate and the exposed underside of the EPDM sheet so as to provide an even and uniform film thickness. Stop bonding adhesive short of splice area. Allow bonding adhesive to flash off until tacky. Flash off time will vary depending on ambient air temperature.
- D. Roll the previously coated EPDM sheet into the coated underlayment substrate slowly and evenly so as to minimize wrinkles. Broom the membrane with a stiff broom to ensure proper contact.
- E. Clean the lap splice area with the manufacturer's splice wash/cleaner/primer. Use splice tape to mate the two laps. Allow the top sheet to fall freely onto the bottom sheet so as not to stretch or wrinkle the membrane. Apply pressure and roll the splice with a steel roller.
- F. Follow the manufacturer's instructions for installing and splicing the EPDM membrane.
- G. Staging of the roof membrane application or temporary membrane is not acceptable. All exposed underlayment must be covered with the completed roof membrane system.

- H. Always install water cut-offs at the end of each day's work to prevent moisture from getting into and under the completed roof membrane and be sure to remove the water cut-offs prior to continuing the roofing application process.
- I. Follow Manufacturer's specification guidelines for installing membrane in temperatures below 40 degrees Fahrenheit.

### 3.06 FLASHING INSTALLATION

#### A. Base flashing at walls and roof curbs.

1. Apply bonding adhesive to the flashing substrate and the exposed underside of the EPDM flashing sheet so as to provide an even, uniform film thickness. Stop bonding adhesive short of splice area. Allow bonding adhesive to flash off until tacky. Flash off time will vary depending on ambient air temperature.
2. Roll the previously coated EPDM flashing sheet into the coated flashing substrate slowly and evenly so as to minimize wrinkles. Apply pressure and roll the flashing sheet with a steel roller to ensure proper contact.
3. Clean the splice area between the EPDM flashing sheet and the EPDM membrane with the manufacturer's splice wash/cleaner/primer. Use splice adhesive to mate the two sheets. Allow the top sheet to fall freely onto the bottom sheet so as not to stretch or wrinkle the membrane. Apply pressure and roll the splice with a steel roller.
4. Apply uncured EPDM to the corners of the power ventilator curbs in a similar manner as above. Use two pieces of uncured EPDM at each corner as per the manufacturer's requirements.
5. Follow all Manufacturer's specification and warranty requirements for flashing installation.

#### B. Contractor shall flash all flanged metal components in the following manner:

1. Clean the EPDM membrane and the metal edge and apply manufacturer's primer/cleaner and allow to flash off.
2. Apply manufacturer's "peel and stick" type flashing tape and roll with a steel hand roller.
3. Lap adjacent pieces of flashing tape a minimum of 1".
4. Follow all Manufacturer's specification and warranty requirements for flashing installation.

### 3.07 ROOF DRAIN FLASHING INSTALLATION

- A. Run EPDM membrane into drain sump.
- B. Install manufacturer's water block sealant underneath EPDM membrane, before installing clamping ring.
- C. All bolts must be in place and properly secured. Tighten the clamping ring bolts to achieve constant compression.
- D. Follow all manufacturer's specification requirements for flashing and installing roof drain inserts.

### 3.08 VENT PIPE FLASHING INSTALLATION

- A. Clean and prime EPDM membrane around vent pipe.
- B. Slip pre-fabricated EPDM pipe flashing over vent pipe, cut to proper height.
- C. Remove release paper from underside of pre-fabricated pipe flashing and press on to EPDM membrane. Apply pressure and roll the splice with a steel roller.
- D. Install a stainless steel clamping ring at the top of the pre-fabricated pipe flashing and seal with lap sealant.
- E. Follow all manufacturer's specification requirements for flashing vent pipes.

### 3.09 CLEANING

- A. Remove drippage of bitumen and adhesive from all walls, windows, floors, ladders, and finished surfaces.
- B. In areas where finished surfaces are soiled by asphalt or any other sources of soiling caused by work of this section, consult manufacturer of surfaces for cleaning advice and conform to their instructions.

END OF SECTION

## SECTION 07620

### SHEET METAL FLASHING AND TRIM

#### PART 1 GENERAL

##### 1.01 SECTION INCLUDES

- A. Copper flashings.
- B. Miscellaneous flashings (i.e, rain collars, chimney cap, etc.)
- C. Pre-finished aluminum shingle repair panels.

##### 1.02 QUALITY ASSURANCE

- A. Perform Work in accordance with the following:
  - 1. NRCA (National Roofing Contractors Association) Roofing and Waterproofing Manual.
  - 2. Manufacturer's printed instructions.
  - 3. SMACNA - Architectural Sheet Metal Manual.
  - 4. SPRI (Single Ply Roofing Institute) Flexible Membrane Roofing: A Professional's Guide to Specifications.
  - 5. Factory Mutual Loss Prevention Data Sheet 1-49, Perimeter Flashing.
  - 6. Applicator shall be company specializing in sheet metal flashing work with at least 5 years experience.

##### 1.03 SUBMITTALS

- A. Prior to the start of any roofing work, the Contractor shall submit the following to the Owner's representative:
  - 1. A list of materials intended for use on this project.
  - 2. Copies of Manufacturer's specifications and current product literature.
  - 3. Samples of each component to be used in the roof system.
  - 4. Sample copy of Contractor's Warranty.
  - 5. Sample copy of Manufacturer's Warranty.
  - 6. Certification that the Contractor is an approved Applicator of the system intended for use.
  - 7. Certification by the Manufacturer that all materials supplied comply with all requirements of the identified ASTM and industry standards or practices.
  - 8. Technical acceptance by the Manufacturer of Contract Specifications and Drawings.
  - 9. Certification from the Manufacturer that the system specified meets all identified code and insurance requirements.

#### 1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Handle all materials to prevent damage. Stack pre-formed and pre-finished material to prevent twisting, bending, or abrasion, and to provide ventilation.
- B. All materials which are deemed to be damaged by the Owner's representative are to be removed from the job site and replaced at no cost to the Owner.

#### 1.06 JOB CONDITIONS

- A. Do not apply sheet metal materials during inclement weather.

#### 1.07 WARRANTIES

- A. Work of this section shall be covered under Contractors warranty specified in Section 07311.

### PART 2 PRODUCTS

#### 2.01 SHEET MATERIALS

- A. Copper: 20 oz. cold rolled copper, equal to ASTM B370, Copper Sheet and Strip for Building Construction.

#### 2.02 ACCESSORIES

- A. Fasteners
  - 1. Sheet metal to wood (unexposed): 3/8" head, annual threaded, galvanized roofing nails, 11 gauge ring shank, sufficient to penetrate 1" minimum into wood.
  - 2. Sheet metal to wood (exposed): Shall be minimum No. 8 screws and shall penetrate minimum 1-1/2" into wood. Screws shall have neoprene washers under head.
  - 3. Metal to concrete or masonry: Buildex Tapcon or Rawl threaded anchors, 3/16" minimum diameter and shall penetrate minimum 1-1/2" through the concrete or masonry. Screws shall have a neoprene washer under head.
  - 4. Sheet metal to sheet metal: Self-tapping sheet metal screws of minimum 1/2" length and #3 diameter. Exposed screws shall have a neoprene washer under head.
- B. Metal Primer: ASTM D 41, asphalt primer.
- C. Flashing Cement: ASTM D 4586 Type I - Asbestos free.

## D. Sealants:

1. Butyl Tape: Pre-formed polyisobutylene Cushion Lock CL-50 non hardening, self-adhering tape.
2. Elastomeric Sealant: Silicone sealant (masonry-to-masonry joints): Ultra-low-modulus, one part, neutral cure silicone sealant complying with ASTM C-920, Type S, Grade NS, Class 100/50, Use T, NT, M, G, A, and O, equal to Dow Corning 790 Silicone Building Sealant.
3. Elastomeric Sealant: Silicone Sealant (metal to metal): One part silicone sealant complying with Federal Specification No. TT-S-001543A, Type II, Class A; ASTM C-920, Type S, Class 25, Grade NS.

E. Solder and Flux: Solder ASTM B32 Type recommended for materials being used; flux Federal Specification O-F-506C, Type I, Form A or B, 50/50 or better.

F. Ice and Water Shield Membrane: W.R. Grace "Ice & Water Shield", ASTM D1970, sheet barrier of self-adhering, rubberized asphalt bonded to sheet polyethylene, 58 mil total thickness, with strippable treated release paper. *NO SUBSTITUTIONS PLEASE!*

G. Rosin paper: Standard red rosin building paper.

## 2.04 FABRICATION

- A. Form components true to shape, accurate in size, square, and free from distortion or defects.
- B. Custom fabricate all gutters, downspouts, gravel stop, etc. by obtaining field dimensions for accurate fit.
- C. Form sections in 10' lengths. Make allowances for expansion at joints.
- D. Fabricate continuous cleats of same material as fascia, gravel stop, or coping and of equal or greater thickness.
- E. Hem exposed edges on underside 1/2"; miter and seam corners. Fabricate vertical faces with bottom edge formed outward 1/4" and hemmed to form drip.
- F. Fabricate flanged flashings to allow flanges to extend at least 4" over roofing.
- G. Fabricate, miter rivet, solder, etc. corners in one piece, 12" in each direction from a corner.

## 2.05 FINISH

- A. Back-paint concealed metal surfaces with protective backing paint where expected to be in contact with cementitious materials or dissimilar metals.
- B. Copper will be supplied in the natural "salmon reddish brown" color as supplied by the mill. The copper surface will be free of all water staining and weather oxides.

## PART III EXECUTION

### 3.01 EXAMINATION AND PREPARATION

- A. Field measure site conditions prior to fabricating work.
- B. Verify membrane termination and base flashings are in place, sealed, and secured. Verify roof openings, curbs, pipes, etc. are in place and solidly set.

### 3.02 INSTALLATION - GENERAL

- A. Conform to Drawing Details and SMACNA manual.
- B. Install continuous cleats as required.
- C. Secure sheet metal flashings in place using concealed fasteners whenever possible.
- D. Set flanges of sheet metal flashings in a bed of roof cement over finished roof plies.
- E. Fit components tight in place. Make corners square, surfaces true and straight in planes, and lines accurate to profiles.
- F. All solder metal joints shall be soldered watertight for full metal surface contact. After soldering, wash metal clean with neutralizing solution and rinse with water.
- G. Contractor shall clean/remove all bituminous or other markings from finished sheet metal surfaces.

END OF SECTION

**SECTION 07711****ROOF AND GUTTER CABLE DEICING SYSTEM****PART 1 GENERAL****1.01 SCOPE OF WORK**

- A. Furnish and install a complete UL listed system of specified heater, components, and controls listed, specifically for roof, gutter, and downspout deicing applications.

**1.02 QUALITY ASSURANCE**

- A. Perform Work in accordance with the following:

1. NRCA (National Roofing Contractors Association) Roofing and Waterproofing Manual.
2. Manufacturer's printed instructions.
3. SMACNA - Architectural Sheet Metal Manual.
4. Underwriters Laboratories.
5. Applicator shall be company specializing in heating cable installation work with at least 5 years experience.

**1.02 SUBMITTALS**

- A. Prior to the start of any roofing work, the Contractor shall submit the following to the Owner's representative:
1. A list of materials intended for use on this project.
  2. Copies of Manufacturer's specifications and current product literature.
  3. Samples of each component to be used in the roof system.
  4. Sample copy of Contractor's Warranty.
  5. Sample copy of Manufacturer's Warranty.
  6. Certification that the Contractor is an approved Applicator of the system intended for use.
  7. Certification by the Manufacturer that all materials supplied comply with all requirements of the identified ASTM and industry standards or practices.
  8. Technical acceptance by the Manufacturer of Contract Specifications and Drawings.
  9. Certification from the Manufacturer that the system specified meets all identified code and insurance requirements.

#### 1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- C. Handle all materials to prevent damage. Stack pre-formed and pre-finished material to prevent twisting, bending, or abrasion.
- D. All materials, which are deemed to be damaged by the Owner's representative, are to be removed from the job site and replaced at no cost to the Owner.

#### 1.06 JOB CONDITIONS

- A. Do not apply materials during inclement weather.

#### 1.07 WARRANTIES

- A. Provide Contractor's two-year workmanship guarantee.

### PART 2 PRODUCTS

#### 2.01 HEATING (DEICING) CABLE

- A. The heating cables will be self-regulating heaters with a power output at 208 volts of 10 watts/foot when exposed to ice or snow at 32°F and a power output of no more than 5 watts per foot at 32°F when dry.
- B. Standard pipe heating cable will not be acceptable unless it has a UL listing specifically for roof deicing applications.
- C. The heating cable will be UL listed to operate at voltages from 208 to 277 volts.

#### 2.02 ACCESSORIES

- A. Thermostat: As recommended by the heating cable deicing system manufacturer.
- B. Snow/Moisture Sensor: As recommended by the heating cable deicing system manufacturer
- C. Ground Fault Circuit Breaker: Must have a 30-milliamp trip level.
- D. Downspout Hangars: As recommended by the heating cable deicing system manufacturer.
- E. Roof Clips: Must be slate specific and as recommended by the heating cable deicing system manufacturer.

## PART 3 EXECUTION

### 3.01 HEATING CABLE INSTALLATION

- A. Heater shall be loose laid in gutters in a double pass. Cable shall be suspended in downspouts as a loop and held in place by system specific downspout hangars.
- B. Heating cable shall be run 18" up on roof on 2'-6" spacing and secured to slate shingles with slate specific clips.
- C. Install thermostat, snow/moisture sensors, and ground fault circuit breakers as required.
- D. Follow all heating cable deicing system manufacturer's application instructions.
- E. Hard wiring hooks up to be the responsibility of the Owner.

### 3.02 TESTING

- A. After installation, test the dielectric jacket's insulation resistance and continuity with a 2500 VDC megger. Insulation resistance from the conductors to the shield shall be between 20 and 1000 megohms.

END OF SECTION

Attachment: AHPC CofA Application Part I (9-30-2023) (28304 : St. Mary's)



Overview photo



Overview photo.



Overview photo.



Photo of existing slate taken May of 2022.



Photo of existing slate taken in May of 2022.



Photo of existing slate taken in May of 2022.



Photo of existing slate taken in May of 2022.



Photo of existing slate taken in May of 2022.

LEGEND

|       |      |                        |
|-------|------|------------------------|
|       | ---- | FENCE AS NOTED         |
|       | □    | SIGN                   |
| GP    | △    | GUARD POSTS            |
| FP    | ○    | FLAG POLE              |
| GAS   | □    | GAS METER              |
| DI    | □    | DRAINAGE INLET         |
| ST MH | ○    | STORM MANHOLE          |
| SA MH | ○    | SANITARY MANHOLE       |
| CO    | ○    | CLEANOUT               |
|       | ★    | LIGHT STANDARD         |
| EM    | □    | ELECTRIC METER         |
| EMH   | ○    | ELECTRIC MANHOLE       |
| UP    | ○    | UTILITY POLE           |
| UPL   | ○    | UTILITY POLE W/ LIGHT  |
| OHW   | —    | OVERHEAD WIRES         |
| FLT   | □    | FLOOD LIGHT            |
| TJB   | □    | TELEPHONE JUNCTION BOX |
| WV    | +    | WATER VALVE            |
|       | □    | HYDRANT                |
| CONC  |      | CONCRETE               |
| L     |      | LIBER                  |
| P     |      | PAGE                   |
| I.P.  |      | IRON PIPE              |
| RYD   | ○    | REAR YARD DRAIN        |
| STY   |      | STORY                  |
| H.C.  |      | HANDICAPPED            |
| REG   |      | REGULAR                |
| MAG.  |      | MAGNESIUM              |
| GW    |      | GUY WIRE               |
| WW    |      | WINDOW WELL            |

PARCEL DESCRIPTION:

ALL THAT TRACT OR PARCEL OF LAND SITUATE IN THE TOWN OF AMHERST, COUNTY OF ERIE AND STATE OF NEW YORK, BEING PART OF LOT NO. 6, TOWNSHIP 12, RANGE 7 OF THE HOLLAND LAND COMPANY'S SURVEY, DESCRIBED AS FOLLOWS:

COMMENCING AT A POINT IN THE WEST LINE OF MILL STREET (66 FEET WIDE) AT THE INTERSECTION OF SAME WITH THE SOUTH LINE OF SUBLOT NO. 16 AS SHOWN ON A MAP RECORDED IN THE ERIE COUNTY CLERK'S OFFICE IN LIBER 225 OF DEEDS AT PAGE 336, THENCE SOUTHERLY ALONG SAID WEST LINE OF MILL STREET, A DISTANCE OF 220.59 FEET TO A POINT, THENCE WESTERLY AT RIGHT ANGLES TO SAID WEST LINE OF MILL STREET, A DISTANCE OF 287.23 FEET TO A NORTHEAST CORNER OF LANDS OF THE TOWN OF AMHERST AS RECORDED IN THE ERIE COUNTY CLERK'S OFFICE IN LIBER 10961 OF DEEDS AT PAGE 9821; THENCE CONTINUING ALONG SAID NORTH LINE OF LANDS OF THE TOWN OF AMHERST WHICH FORMS AN ANGLE TO THE LEFT OF 158°13'49" FROM THE LAST MENTIONED LINE, A DISTANCE OF 50.74 FEET TO THE PRINCIPAL POINT OR PLACE OF BEGINNING, THENCE SOUTHWESTERLY AT RIGHT ANGLES TO THE LAST MENTIONED LINE, A DISTANCE OF 286.17 FEET TO A POINT, THENCE SOUTHWESTERLY AT AN INTERIOR ANGLE OF 124°11'53", A DISTANCE OF 215.00 FEET TO A POINT IN THE SOUTH LINE OF SAID LANDS OF THE TOWN OF AMHERST; THENCE CONTINUING SOUTHWESTERLY ALONG SAID SOUTH LINE OF THE LANDS OF THE TOWN OF AMHERST, A DISTANCE OF 165.30 FEET TO A POINT, THENCE NORTHWESTERLY ALONG A LINE WITH AN INTERIOR ANGLE OF 119°26'19", A DISTANCE OF 169.96 FEET TO A CORNER IN THE WEST LINE OF SAID LANDS OF THE TOWN OF AMHERST; THENCE NORTHERLY ALONG THE WEST LINE OF SAID LANDS OF THE TOWN OF AMHERST AN INTERIOR ANGLE OF 138°07'59", A DISTANCE OF 140.00 FEET TO A POINT, THENCE NORTHEASTERLY ALONG SAID LANDS OF THE TOWN OF AMHERST AN INTERIOR ANGLE OF 135°, A DISTANCE OF 139.47 FEET TO A POINT; THENCE EASTERLY ALONG A LINE FORMING AN INTERIOR ANGLE OF 146°43'40", A DISTANCE OF 278.42 FEET TO A POINT IN THE NORTH LINE OF LANDS OF THE TOWN OF AMHERST; THENCE EASTERLY ALONG THE LANDS OF THE TOWN OF AMHERST FORMING AN INTERIOR ANGLE OF 168°16'20", A DISTANCE OF 33.98 FEET TO A POINT, THENCE CONTINUING ALONG THE NORTH LINE OF LANDS OF THE TOWN OF AMHERST AN INTERIOR ANGLE OF 158°13'49", A DISTANCE OF 200.00 FEET TO A POINT OR PLACE OF BEGINNING, CONTAINING 4.11 ACRES, MORE OR LESS.

PARKING SPACES:

SIZE - 9' X 19'  
8 - HANDICAPPED SPACES  
120 - REGULAR SPACES  
128 - TOTAL PARKING SPACES

FLOOD ZONE DESIGNATION:

SAID DESCRIBED PROPERTY IS LOCATED WITHIN AN AREA HAVING NO SPECIAL FLOOD HAZARD AREA ZONING DESIGNATION BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, ON FLOOD INSURANCE RATE MAP NO. 0012E, WITH A DATE OF IDENTIFICATION OF OCTOBER 16, 1992, FOR COMMUNITY NUMBER 360226, IN ERIE COUNTY, STATE OF NEW YORK, WHICH IS THE CURRENT FLOOD INSURANCE RATE MAP FOR THE COMMUNITY IN WHICH SAID PROPERTY IS SITUATED.

REFERENCE DEEDS:

- 1) LIBER 225, PAGE 336
- 2) LIBER 10961, PAGE 9897
- 3) LIBER 10961, PAGE 9821
- 4) LIBER 11041, PAGE 2533

PREMISES IS SUBJECT TO THE FOLLOW:

- 1) 15' WIDE UTILITY EASEMENT FOR UNDERGROUND ELECTRICAL FACILITIES FOR SERVICE GRANTED TO NIAGARA MOHAWK POWER CORPORATION PER L. 11052, P. 8636
- 2) RIGHT OF WAY AGREEMENT GRANTED TO NATIONAL FUEL GAS DISTRIBUTION CORPORATION PER L. 11055, P. 1673.
- 3) EASEMENTS AND PARTY WALL AGREEMENT PER L.11090, P. 8581
- 4A) ACCESS EASEMENT, 4B) UTILITY/ACCESS EASEMENT & 4C) DRAINAGE EASEMENT PER L.11090, P.8601.

ZONING CLASSIFICATION:


ZONE - COMMUNITY FACILITIES DISTRICT (CF)

FOR FURTHER INFORMATION CONTACT TOWN OF AMHERST CODE ENFORCEMENT OFFICER WILLIAM PIGEON AT 716-631-7080.

| MINIMUM SETBACK REQUIREMENTS FOR YARD          | STRUCTURES | PARKING, LOADING & STACKING AREAS |
|------------------------------------------------|------------|-----------------------------------|
| FRONT, FROM RIGHT-OF-WAY OF A DEDICATED STREET | 50 FEET    | 15 FEET                           |
| SIDE, ABUTTING A RESIDENTIAL DISTRICT          | 25 FEET    | 10 FEET                           |
| REAR, ABUTTING A NONRESIDENTIAL DISTRICT       | 15 FEET    | 5 FEET                            |


NOTE:

THIS SURVEY WAS PREPARED USING CERTIFICATE OF TITLE ISSUED BY NATIONAL LAND TENURE, L.L.C., TITLE NO. NLT-8063-E-03 DATED JULY 1, 2005



VICINITY MAP

NOT TO SCALE



CERTIFICATION:

I HEREBY CERTIFY TO:  
JPMORGAN CHASEBANK, N.A.,  
THE COMPTROLLER OF THE STATE OF NEW YORK'S TRUSTEE OF THE COMMON RETIREMENT FUND,  
THE STATE OF NEW YORK MORTGAGE AGENCY  
NATIONAL LAND TENURE, L.L.C.  
THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH "MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/ACSM LAND TITLE SURVEYS," JOINTLY ESTABLISHED AND ADOPTED BY ALTA, ACSM AND NSPS IN 1999.  
PURSUANT TO THE ACCURACY STANDARDS AS ADOPTED BY ALTA, NSPS, AND ACSM AND IN EFFECT ON THE DATE OF THIS CERTIFICATION, UNDERSIGNED FURTHER CERTIFIES THAT THE SURVEY MEASUREMENTS WERE MADE IN ACCORDANCE WITH THE "MINIMUM ANGLE, DISTANCE AND CLOSURE REQUIREMENTS FOR SURVEY MEASUREMENTS WHICH CONTROL LAND BOUNDARIES FOR ALTA/ACSM LAND TITLE SURVEY."

Deborah A. Naylor  
DEBORAH A. NAYLOR, P.L.S., P.C.  
REGISTRATION NO. 049659-1  
DATE 7/15/05

CADD2001: \ 2001136 \ ALTA2005.DWG

| DATE OF SURVEY | DATE OF REVISION | COMMENT                                           | DATE OF SURVEY | DATE OF REVISION | COMMENT                          |
|----------------|------------------|---------------------------------------------------|----------------|------------------|----------------------------------|
| 5/5/2003       | 5/26/2004        | ADDED PROPOSED EASEMENTS                          | 5/13/2002      | 11/15/2002       | INCREASE SIZE OF ACCESS EASEMENT |
| 5/5/2003       | 7/27/2004        | CORRECTED EASEMENT DIMENSIONS                     | 5/13/2002      | 11/20/2002       | CHANGE SIZE OF ACCESS EASEMENT   |
| 5/5/2003       | 9/7/2004         | ADDED 3 PROPOSED TOWN OF AMHERST ACCESS EASEMENTS | 5/13/2002      | 4/23/2003        | ADD UTIL. EASEMENT & FLOOD NOTE  |
| 5/5/2003       | 9/14/2004        | CHANGED PROPOSED EASEMENT NO. 3                   | 5/5/2003       | 5/7/2003         | UPDATED TO ALTA/ACSM STANDARDS   |
| 7/7/2005       | 7/7/2005         | UPDATED ALTA/ACSM SURVEY                          | 5/5/2003       | 5/9/2003         | UPDATED CERTIFICATION            |
|                |                  |                                                   | 5/5/2003       | 12/16/2003       | ADDED PROPOSED DRAINAGE EASEMENT |
|                |                  |                                                   | 5/5/2003       | 2/12/2004        | ADDED NEW UTILITIES AND PAVEMENT |
|                |                  |                                                   | 5/5/2003       | 3/11/2004        | UPDATED SURVEY                   |
|                |                  |                                                   | 5/5/2003       | 12/16/2003       | ADD DUMPSTER PAD                 |
|                |                  |                                                   | 5/5/2003       | 3/23/2004        | ADD EMERGENCY GENERATOR PAD      |
|                |                  |                                                   | 5/5/2003       | 5/11/2004        | FIELD CHECKED PARKING LOTS       |

ALTA/ACSM SURVEY  
PART OF LOT 6, TOWNSHIP 12, RANGE 7  
OF THE HOLLAND LAND COMPANY'S SURVEY  
TOWN OF AMHERST  
COUNTY OF ERIE, STATE OF NEW YORK

Deborah A. Naylor PLS, P.C.  
Land Surveying - Land Planning  
1490 Church Street  
Alden, New York 14004


Ph: (716) 937-9448 Fax: (716) 937-9526

DATE: 5/13/2002 SHEET: 1 OF 1 DWN BY: DMS

JOB NO.: 2001136 SCALE: 1" = 40' CHK'D BY: DAN

WARNING: ALTERING THIS DOCUMENT IS IN VIOLATION OF THE LAW EXCEPTING AS PROVIDED IN SECTION 7209, PART 2 OF THE NEW YORK STATE EDUCATION LAW.

THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF AN ABSTRACT OF TITLE AND IS SUBJECT TO ANY STATEMENT OF FACTS THAT MAY BE REVEALED BY AN EXAMINATION OF SUCH.



THE BROWNE COMPANY


Roofing and Waterproofing Consultants, Inc.

98 FOREST DRIVE, ORCHARD PARK, NEW YORK 14127

PHONE: 716-667-0802 EMAIL: BROWNECO@AOL.COM

Attachment: AHPC CofA Application Part II (9-30-2023) (28304 : St. Mary's)

IN THE OUTLINED AREA,  
SLATE SHINGLES WERE REMOVED,  
NEW WOOD DECKING INSTALLED,  
NEW ICE & WATER SHIELD INSTALLED,  
& SHINGLES WERE INSTALLED  
ROOFER WOULD HAVE TO REMOVE  
EXIST. SHINGLES & RE-INSTALL  
ICE & WATER SHIELD



ROOF REHABILITATION NOTES:


- REMOVE EXIST. SLATE & EPDM ROOFING DOWN TO WOOD DECK.
- OVERLAY ENTIRE ROOF WITH 7/16" EXTERIOR GRADE OSB.
- COVER ENTIRE SLOPED AREA WITH NEW W.R. GRACE ICE & WATER SHIELD.
- BASE BID NO. 1 - INSTALL NEW SLATE SHINGLES.
- BASE BID NO. 2 - INSTALL NEW SYNTHETIC SLATE SHINGLES
- BASE BID NO. 3 - INSTALL NEW ARCHITECTURAL ASPHALT (GRAND MANOR) SHINGLES
- INSTALL NEW 5/8" GYP OVERLAYMENT BOARD & .090 EPDM AT FLAT ROOF AREAS.
- REPLACE SLATE SIDING WITH NEW HARDIE BOARD CEMENT FIBER SIDING.
- RE-USE COPPER GUTTERS, COUNTERFLASHINGS, FASCIA, STEP FLASHINGS, & DOWNSPOUTS WHEREVER POSSIBLE
- INSTALL NEW COPPER FLASHINGS WHEN THESE FLASHINGS CAN NOT BE RE-USED.
- CONNECT NEW & OLD DOWNSPOUTS TO EXIST. STORM SEWER RECEIVERS.
- INSTALL NEW HEATING CALBES AT ALL EAVES, GUTTERS, & DOWNSPOUTS, CONNECTION BY OTHERS.

KEY

|            |   |              |   |                 |   |
|------------|---|--------------|---|-----------------|---|
| HVAC Unit  |   | Pipe/Conduit | * | Not In Contract |   |
| Roof Drain | • | Roof Hatch   |   | Flat Roof Area  | F |
| Vent Pipe  | o | Stack        | ⊗ |                 |   |


ST. MARY'S COMMONS APARTMENTS  
ROOF REHABILITATION PROJECT  
400 MILL STREET, WILLIAMSVILLE, NY

|                        |             |          |
|------------------------|-------------|----------|
| TITLE ROOF PLAN        |             |          |
| DRAWN BY GPB           |             |          |
| CHECKED                |             |          |
| CHK'D BY               |             |          |
| DATE: 09-14-23         |             |          |
| FILE NAME ST MARYS - 1 |             |          |
| SCALE                  | PROJECT NO. | DWG. NO. |
| 1/32" = 1'-0"          |             | 1 4      |
|                        |             | SHEET OF |




NOTE - RE-USE EXISTING COPPER GUTTERS & DOWNSPOUTS WHEREVER POSSIBLE


1/2 DETAIL AT EAVES/GUTTER



3/2 DETAIL AT FLAT-TO-SHINGLE TRANSITION



2/2 FLASHING AT BUILT-IN GUTTER




- NOTES:
- SHINGLES MUST LAP OVER EPDM MEMBRANE A MINIMUM OF 2 FULL COURSES.
  - A PROPER STARTER COURSE (WITH ADHESIVE AT THE BOTTOM EDGE) MUST BE INSTALLED.

4/2 DETAIL AT SHINGLE-TO-FLAT ROOF INTERSECTION


THE BROWNE COMPANY  
Roofing and Waterproofing Consultants, Inc.  
98 FOREST DRIVE, ORCHARD PARK, NEW YORK 14127  
PHONE: 716-667-0802 EMAIL: BROWNECO@ADELPHIA.NET  
Attachment: AHPC CofA Application Part II (9-30-2023) (28304 : St. Mary's)

| ST. MARY'S COMMONS APARTMENTS<br>ROOF REHABILITATION PROJECT<br>400 MILL STREET, WILLIAMSVILLE, NY |             |                       |
|----------------------------------------------------------------------------------------------------|-------------|-----------------------|
| TITLE    ROOF FLASHING DETAILS (1)                                                                 |             |                       |
| DRAWN BY    GPB                                                                                    |             |                       |
| CHECKED                                                                                            |             |                       |
| CHK'D BY                                                                                           |             |                       |
| DATE: 09-14-23                                                                                     |             |                       |
| FILE   NAME   ST MARYS - 2                                                                         |             |                       |
| SCALE                                                                                              | PROJECT NO. | DWG. NO.              |
| NOT TO SCALE                                                                                       |             | SHEET    2    OF    4 |




NOTE - REMOVE EXIST. COPPER COUNTERFLASHING


1/3 FLASHING DETAIL AT INTERSECTION WITH MASONRY




2/3 FLASHING DETAIL AT RAKE EDGES



3/3 FLASHING DETAIL AT VALLEYS



4/3 FLASHING DETAIL AT NEW SIDING



NOTE - RE-USE EXISTING COPPER DOWNSPOUTS WHEREVER POSSIBLE

5/3 FLASHING DETAIL AT BUILT-IN GUTTER SCUPPERS

THE BROWNE COMPANY


Roofing and Waterproofing Consultants, Inc.

98 FOREST DRIVE, ORCHARD PARK, NEW YORK 14127

PHONE: 716-667-0802 EMAIL: BROWNECO@ADELPHIA.NET


Attachment: AHPC CofA Application Part II (9-30-2023) (28304 : St. Mary's)

| ST. MARY'S COMMONS APARTMENTS<br>ROOF REHABILITATION PROJECT<br>400 MILL STREET, WILLIAMSVILLE, NY |             |                          |
|----------------------------------------------------------------------------------------------------|-------------|--------------------------|
| TITLE    ROOF FLASHING DETAILS (2)                                                                 |             |                          |
| DRAWN BY    GPB                                                                                    |             |                          |
| CHECKED                                                                                            |             |                          |
| CHK'D BY                                                                                           |             |                          |
| DATE: 09-14-23                                                                                     |             |                          |
| FILE NAME   ST MARYS - 3                                                                           |             |                          |
| SCALE                                                                                              | PROJECT NO. | DWG. NO.                 |
| NOT TO SCALE                                                                                       |             | SHEET    3       OF    4 |




NOTE - RE-USE EXISTING COPPER GUTTERS & DOWNSPOUTS WHEREVER POSSIBLE

1/4 FLASHING DETAIL AT GUTTER




NOTE - REMOVE EXIST. COPPER COUNTERFLASHING

2/4 FLASHING DETAIL AT WALL



3/4 FLASHING DETAIL AT ROOF EDGE



NOTE - RE-USE EXISTING COPPER GUTTERS & DOWNSPOUTS WHEREVER POSSIBLE

4/4 FLASHING DETAIL AT SCUPPERS

THE BROWNE COMPANY

Roofing and Waterproofing Consultants, Inc.

98 FOREST DRIVE, ORCHARD PARK, NEW YORK 14127

PHONE: 716-667-0802      EMAIL: BROWNECO@ADELPHIA.NET

Attachment: AHPC CofA Application Part II (9-30-2023) (28304 : St. Mary's)

| ST. MARY'S COMMONS APARTMENTS<br>ROOF REHABILITATION PROJECT<br>400 MILL STREET, WILLIAMSVILLE, NY |             |                       |
|----------------------------------------------------------------------------------------------------|-------------|-----------------------|
| TITLE    ROOF FLASHING DETAILS (3)                                                                 |             |                       |
| DRAWN BY    GPB                                                                                    |             |                       |
| CHECKED                                                                                            |             |                       |
| CHK'D BY                                                                                           |             |                       |
| DATE: 09-14-23                                                                                     |             |                       |
| FILE NAME    ST MARYS - 4                                                                          |             |                       |
| SCALE                                                                                              | PROJECT NO. | DWG. NO.              |
| NOT TO SCALE                                                                                       |             | SHEET    4    OF    4 |



EcoStar LLC  
42 Edgewood Drive  
Holland, NY 14080  
800.211.7170  
EcoStarLLC.com

Find us on social media:



# Synthetic Slate & Shake Roofing

Durable, sustainable  
building product



Made with recycled  
polymer and rubber  
(not tires)



Less than half the  
weight of natural slate



Class C and Class A  
fire ratings available



Class 4 hail impact  
resistance rating



50-year transferable  
warranty available

Design Your Roof,  
Your Way



www.ecostarllc.com



Majestic Niagara Slate 12" in Stormy Gray Blend



Highly Sustainable | Highest Testing Performance | Proven Longevity | Uncompromised Beauty

Proudly Made in the USA

Packet Pg. 80



Thank you for your interest in EcoStar

For 30 years, EcoStar has been a pioneer in the synthetic slate and shake roofing markets. We pride ourselves in making products that turn everyday steep-slope roofs into extraordinary extensions of our customers' visions. Our team has long been in place ensuring all our products perform at the highest level. We have followed a stringent quality program since 1997 and are audited every 6 months in accordance with ISO 9001, UL and other certification agencies.

EcoStar is dedicated to helping the world address recyclable materials. Since 1993, we have redirected thousands of tons of valuable raw materials away from landfills each year. By using post-industrial upcycled materials, EcoStar tiles aid in the preservation of natural resources. No trees are cut down and no slates are quarried for the manufacture of EcoStar products.

EcoStar is here for you. If you have a vision for your roof, we can turn it into reality. And you can rest assured that the beauty of your roof will last as long as you call it home.

Why Choose EcoStar?

- Highly Sustainable
- Designed to Perform
- Highest Testing Performance
- Largest Profile Offering
- Unmatched Weathering Capability
- Color Match Excellence
- Proven Longevity
- Easy Installation
- Uncompromised Beauty
- Made in the USA



Contents

|    |                                                                                              |
|----|----------------------------------------------------------------------------------------------|
| 2  | The EcoStar Difference                                                                       |
| 4  | Traditional Slate                                                                            |
| 6  | Niagara Slate                                                                                |
| 8  | Random-Width Blends                                                                          |
| 10 | Features and Benefits:<br>Majestic Slate, Empire Slate and Niagara Slate                     |
| 12 | Traditional Shake                                                                            |
| 14 | Aspen Blend                                                                                  |
| 16 | Niagara Shake                                                                                |
| 18 | Features and Benefits:<br>Seneca Shake, Empire Shake, Empire Shake Plus<br>and Niagara Shake |
| 20 | Color Options                                                                                |
| 22 | Commercial and Historic Applications                                                         |
| 24 | Installation and Accessories                                                                 |
| 25 | Complete Warranty Protection & Custom Projects                                               |

"This is our second project using EcoStar Majestic Slate and our crews love the ease of installation and our customers love the distinctive look on their roofs."

- Alan Frank, Alan Frank Roofing Co.



# The EcoStar Difference

*As the leading manufacturer of sustainable roofing tiles, we recognize the challenges our world faces regarding Earth's limited resources, non-renewable energy sources, and responsible disposition of waste.*

EcoStar LLC leads the composite steep-slope roofing industry with its premium synthetic slate and shake roofing tiles. EcoStar products are made to the highest of standards and are the environmentally-responsible choice for contractors, specifiers, architects and property owners. EcoStar tiles are manufactured in the USA with a material made of up to 80% upcycled post-industrial rubber and plastic.

Over the years, technology has enhanced our already exceptional weathering performance. Product weathering occurs in all synthetic roofing products regardless of material content (recycled or virgin). Our lot control methods ensure that our tiles weather uniformly, so that over time, EcoStar tiles lose their slight sheen and develop a patina, continuing the replication of their natural counterparts. Testing our products remains paramount to providing products that look beautiful and realistic when first installed, and even more natural with each year of exposure to mother nature. In other words, we improve with age!

*Manufactured in strict adherence to ISO 9001 Quality Management Standards.*



EcoStar LLC—pioneers of sustainable roofing since 1993.



1.b

Attachment: AHPC CoFA Application Part II (9-30-2023) (28304 : St. Mary's)

## upcycle

*transitive verb*

: to recycle (something) in such a way that the resulting product is of a higher value than the original item : to create an object of greater value from a discarded object of lesser value.



**20-Year Old Roof**  
Majestic Slate 12" in  
Midnight Gray

# Traditional Slate


## The enduring beauty of slate.

An affordable and environmentally friendly alternative to natural slate, our Traditional Slate lines of recycled roof tiles capture the beauty of natural slate. Traditional Slate is available in single widths (10" and 12"), Designer Tiles (Beveled Edge, Chisel Point and Beaver Tail) and a Random-Width Blend (6", 9" and 12").

Featured image: Majestic Slate 12" in Federal Gray



From left to right: Majestic Slate Beaver Tail in Midnight Gray, Mountain Plum and Chestnut Brown; Majestic Slate 12" in Chestnut Brown; Majestic Slate 12" in Twilight Blend



Featured tiles: Majestic Slate 12" in Smoke Gray, Federal Gray and Stone Red



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Niagara Slate

The thickest, most natural-looking slate profile.

Bigger is better when it comes to Niagara Slate, EcoStar’s largest profile slate, designed to create enhanced shadow lines for maximum aesthetic appeal. Niagara Slate is available in single widths (10", 12" and 14") and a Random-Width Blend.

Featured image: Majestic Niagara Slate 14" in Chestnut Brown



From left to right: Majestic Niagara Slate 12" in Stormy Gray Blend; Majestic Niagara Slate 14" in Chestnut Brown; Majestic Niagara Slate 12" in Midnight Gray



Featured tiles:  
Majestic Niagara Slate  
in Federal Gray,  
Mountain Plum and  
Smoke Gray



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Random-Width Blends

## The most realistic slate blends.

Random-Width Blends are available in both Traditional and Niagara product lines. Traditional Random-Width Blend includes 6", 9" and 12" Majestic Slate or Empire Slate tiles. Niagara Random-Width Blend includes 10", 12" and 14" Majestic Niagara Slate or Empire Niagara Slate tiles. An even number of each size tile is included in every bundle for ease of installation on-site. With straight and staggered installation options, these blends provide the look you desire and the protection you need.

Featured image: Majestic Niagara Slate Random-Width Blend in Black



From left to right: Majestic Slate Random-Width Blend in Earth Green; Majestic Niagara Slate Random-Width Blend in Black; Majestic Niagara Slate 14" and 12" Blend in Black



Featured tiles: Majestic Slate Random-Width Blend in Midnight Gray



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Innovative Design, Classic Slate Look


## EcoStar Slate

Post-industrial recycled compounds are utilized to create a lightweight and environmentally responsible alternative to natural slate. An EcoStar roof offers beautiful, yet proven protection for your most prized investment. It is an inspiration to homeowners looking for affordable style and uncompromised performance.


### Significant advantages:

- Weighs significantly less than natural slate
- Protects against extreme weather conditions
- Reduces need for maintenance and repair
- Lessens environmental impact
- Exceeds industry performance standards
- 50-year warranty

### Profiles



### Majestic Standard Colors



Color samples may not accurately represent the true color level or variations of color blends that will appear on the roof. Colors and specifications subject to change without notice. EcoStar is not liable for color variations or shading.



Looking for a more unique look?  
Achieve a custom look by combining multiple profiles and/or colors. See page 20 to learn more.

All EcoStar products are factory pre-blended for both color and width.

## The right tile for any property

Whether you are looking to elevate the look of a residential property, meet the performance needs of a commercial property, or preserve the look of a historical property, EcoStar offers the right tile.

### Majestic Slate

EcoStar's original eco-friendly tile, made of 80% recycled materials, meeting the needs of most residential applications.

### Empire Slate

The same classic slate look as Majestic Slate with additional energy-saving benefits, and design features that meet the needs of commercial and historical properties.

### Niagara Slate

Niagara Slate is available in the Majestic and Empire formulas and offers an increased tile size and thickness for enhanced shadow lines and increased aesthetic appeal.


Our slates replicate real slate in so many ways - the beauty and durability, the slight sheen after installation, and the gentle patina of the surface over time.

| Tile Features                         | Majestic Slate      |                     | Empire Slate        |                     |
|---------------------------------------|---------------------|---------------------|---------------------|---------------------|
|                                       | Traditional         | Niagara             | Traditional         | Niagara             |
| Recycled Material                     | 80%                 | 80%                 | 25%                 | 25%                 |
| Tile Widths                           | 12", 10", 9", 6"    | 14", 12", 10"       | 12", 10", 9", 6"    | 14", 12", 10"       |
| Profile                               | Solid               | Cavity-back         | Solid               | Cavity-back         |
| Tile Thickness                        | 1/4"                | 5/8"                | 1/4"                | 5/8"                |
| Reveal                                | 7", 6"              | 10", 9"             | 8", 7", 6"          | 10", 9"             |
| Weight per Square (at maximum reveal) | 275 lbs. (12" tile) | 250 lbs. (14" tile) | 308 lbs. (12" tile) | 290 lbs. (14" tile) |
| Fire Rating                           | Class C             | Class C             | Class C/A           | Class C/A           |
| Impact Rating                         | Class 4             | Class 4             | Class 4             | Class 4             |
| Miami-Dade                            | No                  | No                  | Yes                 | Yes                 |
| Standard Colors                       | 12                  | 12                  | 14                  | 14                  |
| Cool Roof Colors                      | No                  | No                  | 11                  | 11                  |
| Custom/Marbled Colors                 | No                  | No                  | Yes                 | Yes                 |
| Designer Tiles                        | Yes                 | No                  | Yes                 | No                  |

### Cool Colors

Enjoy additional energy savings from our line of Cool Colors, available in all Empire colors. (excludes Bedford Black, Tioga Terra Cotta and Plymouth Patina)

### Empire Standard & Cool Colors



"EcoStar synthetic slate was just what we were looking for. We were able to select the size, shape, and blend of colors required to give our home the look of a well-preserved nineteenth-century structure."

- Jay Panzer, Homeowner

EcoStar representatives are available for information about energy savings and homeowners insurance discounts. Visit our website to find your local representative.

# Color Options to Fit Your Style


## Factory Blends\*

EcoStar provides unlimited potential to enhance the beauty of your property with the option of color blends - available in all product lines. From "Wide-Range" blends, which include multiple shades of the same color, to completely custom multi-color mixes, you can create a striking roof with unique style.

### Slate Color Blends:




Scottish Blend




Tuscan Blend




Napa Blend



Summit Blend



Wood Trail Blend




Sierra Blend

### Wide Range Blends:




Stormy Gray Blend



Twilight Blend




Forest Blend




Canyon Blend


### Shake Color Blends:



Summit Blend



Wood Trail Blend



Sierra Blend

## Marbled Blends

EcoStar offers eight beautiful marbled blends in our Empire product lines. Each blend contains a minimum of 2-3 different marbled tiles offering a unique look for any project. Our marbled blends are also available in solid colors. Ask your representative for more details.



Riverbed



Vineyard




Rolling Meadow




Harvest Hill




Ancient Quarry



Feathered Driftwood



Fresh Cut Cedar



Hunters Creek Blend



## Custom Colors

EcoStar's production team can create slate and shake tiles with unique hues based on samples of material, paint swatches, or Pantone® color numbers that highlight your property. Design ideas for your project are endless.



Majestic Niagara Slate 12" in Stormy Gray Blend

*\* All EcoStar products are factory pre-blended for both color and width.*



Top: Empire Slate 12" in Ancient Quarry

Bottom: Aspen Blend in Fresh Cut Cedar

*"EcoStar is the cream of the crop. From the people who produce it, to the product, and right down to the installation. It's a product made from recycled material with an authentic look, backed by one of the best warranties in the industry."*

**- Ronald Cole, The Roof Connection**

# Commercial and Historic Applications

## Exceeding the demands of commercial properties

As a pioneer of synthetic roofing products since 1993, EcoStar has become a favorite for educational buildings, religious facilities and government projects. Designed with up to 6" headlap for installation integrity, EcoStar roof systems exceed best practice roofing techniques, ensuring the longevity of your roof. All EcoStar products are manufactured under strict adherence to ISO 9001 quality management standards.


## Preservation meets conservation

EcoStar products allow preservationists to match the distinctive look of an original roof while meeting modern day performance expectations, limiting the use of natural resources, reducing waste and minimizing carbon footprint. Focusing on reducing, reusing and recycling promotes the lasting benefits of conservation while allowing us to protect our cultural heritage. EcoStar tiles offer flexible installations, such as staggered and offset, to better match original roof designs. EcoStar has been approved for use in historic preservation projects throughout the United States.

## Features and benefits:

- Weighs significantly less than natural slate
- Requires little-to-no maintenance
- Offers energy-saving cool colors
- Includes up to 80% post-industrial recycled content
- Easy application keeps installation costs down
- May contribute toward LEED certification
- Available in a wide variety of profiles and colors
- 50-year warranty is standard

*Majestic Slate has been widely accepted by preservationists and historians for nearly 30 years.*



Top (Right): Majestic Slate 12" in Stone Red

Bottom: Empire Slate Beveled Edge in Manhattan Midnight Wide Range and Freeport Federal Wide Range

*"Our large, historic home had a very old, deteriorating, and unsightly slate roof that needed frequent repairs. Our new EcoStar Majestic Niagara Slate roof matches the original roof perfectly and restores our home to its former beauty."*  
- **David M., Homeowner**

*"We are so pleased with the look and performance of the roofing."*

- **Bill Ingram, Land Management, Inc.**



Bottom (Left to Right): Majestic Niagara Slate in Sage Green, Cedar Brown and Mountain

Majestic Slate 12" in Midnight Gray and B

Majestic Niagara Slate 12" in Smoke Gray, Federal Gray, Midnight Gray, and Mountain

1.b

Attachment: AHPC CoFA Application Part II (9-30-2023) (28304 : St. Mary's)



# Installation and Accessories

EcoStar's extensive network of Gold Star Applicators have been professionally trained to provide you with a remarkably beautiful installation. Our accessories are designed to complement EcoStar synthetic roofing tiles, and are proven to extend the longevity of a roofing system.

*Our reliable protection encompasses every component of the EcoStar roof installation.*



## Glacier Guard

Glacier Guard is an impermeable self-adhering membrane, offering enhanced protection against moisture penetration. A high-temperature self-adhered membrane is also offered.



## Aqua Guard

Aqua Guard is a versatile roofing underlayment offering a stronger and lighter alternative to traditional felt.



## Ridge Vent

EcoStar offers a continuous tile-over ridge vent that efficiently removes moisture build-up in the attic space of a building.



## EcoStar Fasteners

Our stainless steel fasteners provide superior strength and resistance to corrosion, staining and leaking.

# Complete Warranty Protection

A standard 50-year Limited Material Warranty is offered at no extra charge with the purchase of an EcoStar roof. To ensure that your EcoStar roof will perform at its best, consider the benefits of our transferable 50-Year Gold Star Limited Labor and Material Warranty.

## Standard Warranty

Non-Transferable, Limited Materials

## Gold Star Warranty

Transferable, Limited Labor and Materials

EcoStar representatives are available for information about energy savings and homeowners insurance discounts. Visit our website to find your local representative.

# Custom Projects

Whether you're looking for a custom color or shape, EcoStar has the in-house capability to develop a solution for your unique project.



Island Groove Clay Tile




Saw Cut Tile



Fish Scale Tile

Call us today at **800.211.7170** or visit **[www.ecostarllc.com](http://www.ecostarllc.com)** for more information.



Attachment: AHPC CofA Application Part II (9-30-2023) (28304 : St. Mary's)






A roof that is just as reliable as beautiful; the result of opting for our Gold Star Certified Applicators at every installation.

## Protection Overview

- Miami Dade prolonged and accelerated weathering @ 4,500 hours
- Job lot control produces uniform roof tile weathering
- Miami Dade Wind TAS100 & TAS125 (NOA # 17\_1227\_10)
- UL listed Class C or A fire resistance (UL 790)
- UL Class 4 (highest rating) hail impact resistance (UL 2218)
- ISO 9001:2015 Quality Management Standards
- 50-Year Material Warranty
- 50-Year Transferable Labor and Material Warranty available

## Proudly approved and certified by the following organizations:



Visit [www.ecostarllc.com](http://www.ecostarllc.com) for a complete listing of approvals and certifications.



Top: Majestic Slate 12" in Federal Gray

Bottom: Aspen Blend in Midnight Gray

# GRAND MANOR<sup>®</sup>

## Luxury Roofing Shingles

Attachment: AHPC CofA Application Part III (9-30-2023) (28304 : St. Mary's)

# The Peak of Perfection

Some roofs say more. About you. About your style. About the home that uniquely showcases your life.

Grand Manor says it all with a style and grace that is exceptional from every angle. The luxurious multi-layered laminated shingle replicates the look of slate with the confidence backed by a lifetime warranty.

Your home becomes your castle with one of the heaviest shingles we've ever made. CertainTeed developed Grand Manor to endure all types of weather and always look its best, even on the steepest slopes.

## STRIKING LOOKS

Deep shadows and random tabs are the secrets behind the design genius in Grand Manor. The result is a shingle with the incredibly authentic depth and dimension of slate.

## LASTING BEAUTY

Our exclusive Super Shingle® construction design results in a shingle that, once installed, offers virtually five layers of protection. Made of the industry's most durable roofing materials, you'll have a roof with unsurpassed defense against the elements.

## StreakFighter® PROTECTION

The ultimate in stain protection, CertainTeed's StreakFighter technology uses the power of science to repel algae before it can take hold and spread. StreakFighter's granular blend includes naturally algae-resistant copper to combat the ugly black streaking caused by algae and help your roof maintain its beauty for years to come.

With Grand Manor on your home, you'll have the assurance of being protected by one of CertainTeed's finest, most durable luxury shingles—and the confidence of knowing that whenever you look up at your roof, you'll see something beautiful.



Grand Manor, shown in Gatehouse Slate

NOTE: Due to limitations of printing reproduction, CertainTeed can not guarantee the identical match of the actual product color to the graphic representations throughout this publication.



# Elegance Defined with Style and Grace

## GRAND MANOR®

- Authentic depth and dimension of natural slate
- Dynamic color options
- Super Shangle® construction offers five layers of protection
- Streakfighter® protection against algae

### GRAND MANOR® COLOR PALETTE



Colonial Slate



Gatehouse Slate



Stonegate Gray



Weathered Wood



Black Pearl



Brownstone



Georgian Brick



Sherwood Forest

Attachment: AHPC CofA Application Part III (9-30-2023) (28304 : St. Mary's)

# Strength with Style

## GRAND MANOR®

- Class A fire resistance
- Algae resistance
- 110 MPH wind warranty, upgradeable to 130 MPH
- Lifetime-limited warranty



### SPECIFICATIONS

- Two full-size, fiberglass-based shingles with randomly applied tabs
- Authentic depth and dimension of natural slate
- Virtual five-layer coverage when applied

CertainTeed products are tested to ensure the highest quality and comply with the following industry standards:

#### Fire Resistance:

- UL Class A
- UL certified to meet ASTM D3018 Type 1

#### Wind Resistance:

- UL certified to meet ASTM D3018 Type 1
- ASTM D3161 Class F

#### Tear Resistance:

- UL certified to meet ASTM D3462
- CSA standard A123.5

#### Wind Driven Rain Resistance:

- Miami-Dade Product Control Acceptance: Please reference [www.certainteed.com](http://www.certainteed.com) to determine approved products by manufacturing location.

#### Quality Standards:

- ICC-ES-ESR-1389 & ESR-3537

### WARRANTY

- Lifetime limited transferable warranty against manufacturing defects on residential applications
- 50-year limited transferable warranty against manufacturing defects on group-owned or commercial applications
- **StreakFighter®** 15-year algae-resistance warranty
- 10-year SureStart™ protection
- 15-year 110 MPH wind-resistance warranty
- Wind warranty upgrade to 130 MPH available. CertainTeed starter and CertainTeed hip and ridge required.

See actual warranty for specific details and limitations.



Scan code for  
more information



## Add a Little Accent to Your Roof

For a stylish finishing touch to cap hips and ridges, use Shingle Ridge® accessory—available in colors to match your Grand Manor shingles.

## Color Companion Products™ for Flat Roof Areas

With CertainTeed Flintlastic® SA, you can coordinate flat roof areas like carports, canopies and porches with your main roof. Flintlastic SA is a self-adhering low slope roofing product available in colors that complement some of the most popular CertainTeed shingles.



## The Ultimate in Protection

1.c

## StreakFighter®

Algae Resistance

The ultimate in stain protection.

Those streaks you see on other roofs in your neighborhood? That's algae, and it's a common eyesore on roofing throughout North America. CertainTeed's **StreakFighter** technology uses the power of science to repel algae before it can take hold and spread. **StreakFighter's** granular blend includes naturally algae-resistant copper, helping your roof maintain its curb appeal and look beautiful for years to come.

### Granule with StreakFighter Technology

Ceramic coating

Copper layer

Mineral core




Diagram for illustrative  
purposes only.

## CertaSeal™

Uplift Protection

**CertaSeal™** is a fast-activating modified asphalt sealant with a 20-year record of proven performance. Designed to seal shingles together upon installation, it protects roofs from wind uplift and shingle blow-off so that homes stay safe and dry. It's also engineered to remain flexible after installation, unlike harder sealants that can dry out and crack over time.



Attachment: AHPC CofA Application Part III (9-30-2023) (28304 : St. Mary's)



# Integrity Roof System™

A COMPLETE APPROACH TO LONG LASTING BEAUTY AND PERFORMANCE



With as much care as you take in selecting the right contractor, choosing the right roof system is equally as important. A CertainTeed Integrity Roof System combines key elements that help ensure you have a well-built roof for long-lasting performance.

## 1. Waterproofing Underlayment

The first step in your defense against the elements. Self-adhering underlayment is installed at vulnerable areas of your roof to help prevent leaks from wind-driven rain and ice dams.

## 2. Water-Resistant Underlayment

Provides a protective layer over the roof deck and acts as a secondary barrier against leaks.

## 3. Starter Shingles

Starter Shingles are the first course of shingles that are installed and designed to work in tandem with the roof shingles above for optimal shingle sealing and performance.

## 4. Shingles

Choose from a variety of Good-Better-Best styles to complement any roof design and fit your budget.

## 5. Hip & Ridge Caps

Available in numerous profiles, these accessories are used on the roof's hip and ridge lines for a distinctive finishing touch to your new roof.

## 6. Ventilation

A roof that breathes is shown to perform better and last longer. Ridge Vents, in combination with Intake Vents, allow air to flow on the underside of your roof deck, keeping the attic cooler in the summer and drier in the winter.

learn more at:


[certainteed.com/roofing](https://certainteed.com/roofing)



### CertainTeed


CEILINGS • DECKING • FENCE • GYPSUM • INSULATION • RAILING • ROOFING • SIDING • TRIM  
20 Moores Road, Malvern, PA 19355 Professional: 800-233-8990 Consumer: 800-782-8777 [certainteed.com](https://certainteed.com)

©01/23 CertainTeed, Printed in



IN THE  
SPIRIT OF  
TRADITION

CERTAINTEED  
ROOFING PRODUCTS  
FOR HISTORIC  
RENOVATION



The decision to renovate a historic building is a decision to keep history, and all that we learn from it, alive. And while the merits of historic renovation are never in question, its practicality often is.

Distinct alternative building materials, such as heavyweight asphalt roofing shingles from CertainTeed, can be cost-effective solutions when original materials of construction are no longer available, or are prohibitively expensive. CertainTeed's unique products simulate the rich depth, texture and weight of yesteryear's slate, tile and cedar shakes at substantial savings while preserving the integrity of the original building.

Historic structures throughout America, many listed on the National Register of Historic Places, have been renovated to perfection using CertainTeed asphalt roofing products. In the pages that follow, nine of these monuments display their gloriously renewed aesthetics and reveal their stories. Enjoy, in the spirit of tradition.

## R E S I D E N T I A L

## THE HENRY FORD HOUSE


**D**uring the 1940s, the original green ceramic tile roof of the Henry Ford House in Detroit, Michigan, was removed and replaced with inexpensive asphalt shingles. Over the next fifty years, more strip shingles were installed. In 1993, the owners, Dr. Jerald Mitchell and family, chose Grand Manor Shingle®, a heavyweight asphalt shingle with the look of natural roofing products, in the color Sherwood Forest.

Notes Dr. Mitchell, a preservationist, historian and scientist, “We considered ceramic tile but the cost of labor and materials was very high. I did a lot of research on my own and found that Grand Manor looked as close to tile as possible and was substantially less expensive. And since Grand Manor has been used in the area for historic renovation, obtaining the approval of the Historic Commission of the City of Detroit was not a problem.”

The house, an example of Italian Renaissance Revival architecture, was designed by the firm Malcomson, Higginbotham and Clement, and completed in 1908. Its lavish gardens were created by landscape architect T. Glenn Phillips. A machine shop was built over the garage for the Ford's son, Edsel, who had a passion for automotive design.

While living in this house between 1908 and 1915, Henry Ford developed the Model T, introduced American business to mass production, and conceived his revolutionary wage-price theories.

Located in the prestigious Boston-Edison district of Detroit, the Henry Ford House is a Registered Michigan Historic Site.



The ground-level front windows feature stone arches and extended platforms surrounded by wrought iron grillwork.



Hand-crafted columns and trim in the Italian Renaissance Revival style highlight the main entrance.



Ornate dormer windows extend from the third story on each side of the house.

## THE MONTPELIER WHITE HOUSE



**B**uilt in 1877 and located in Montpelier, Ohio, this magnificent Greek Revival house was nearly destroyed by fire in 1906. Records indicate that neighbors and friends saved the home's contents before the arrival of hand-pulled fire-fighting equipment. The west side of the house is original.

J. D. Hill and his descendants lived in the home for over 100 years. A prominent lawyer and businessman, Hill implemented the town's first lighting and water systems during his term as Montpelier's mayor. He was a delegate to the 1904 Republican National Convention. Following his death, his daughter was the home's sole occupant for decades. During those years, she saw Montpelier transform from a small industrial town centered around the Wabash Railroad to a thriving community of over 4,500 people.

When the home changed hands in 1992, the new owners, Laura and Carlton Gray, decided to restore the house back to its original grandeur. They renovated virtually the entire home themselves including re-plastering the walls, stripping and painting the exterior wood, and refinishing the floors.

Three layers of asphalt shingles and two layers of wood shingles painted green were removed from the roof. The Grays considered reroofing with green Vermont slate but the cost and delivery time ruled them out. Says Laura Gray, "With its chamfered edges, CertainTeed's Carriage House Shingle™ in Sherwood Forest fits our needs for shape and color and also offers us virtually maintenance-free performance."



The cornice window frames and their ornate trim are representative of the Greek Revival style of architecture and are original to the house.



The intricate cornice-supporting brackets for the overhanging roof are also original features.

## THE ROMEO HOUSE

**B**uilt in 1871 and located in Romeo, Michigan, this house is a striking example of Victorian Gothic architecture. Little is known about the home except that it was occupied originally by the town's most prominent builder, George Hipp, and his family.

Always a residence, an addition was built onto the home in the 1920s. In the years that ensued, the home was "modernized" using acoustic tiles and cheap paneling. Virtually all the exterior trim was removed.

In 1992, the run-down home was purchased by local builders with a passion for historic homes, research, details and practicality. Openings in the home's structure provided pieces of the original exterior trim, an invaluable clue to the home's past appearance.

The new windows are the "two-over-two" Victorian Gothic style, the eyebrows over them are hand-bent aluminum. The layers of asphalt shingles and the original cedar shakes were removed from the roof and replaced with CertainTeed's Grand Manor Shingle® in Brownstone, both for its natural looks and limited lifetime warranty.

Owners, Shirley and Lee Engwall, have lived in 11 other houses, but this historic home is clearly their favorite. Says Shirley Engwall, "We've got the best of everything — old world charm and craftsmanship, and next-to-no maintenance."

The home is listed with the Romeo Historic Society.




Although not original to the house, the characteristic Victorian "gingerbread" trim was designed to match existing millwork on vintage homes in the neighborhood.



The porch's millings and posts are square with chamfered edges in keeping with the original architectural style.

## DETROIT FIRE HOUSE NO. 5



A pair of dormer windows adorns the roof on the south side of the firehouse. Deteriorating wood shingles which covered the walls of these dormer windows had to be replaced.

**B**uilt during the Victorian era, this 112-year old building is the former home of the Detroit Fire Department's Ladder Company #5. Used continuously through the 20th Century, the property was recently purchased and renovated by private investors.

The brick firehouse, which was built to serve as an open-air farmers market and the surrounding residential community, sits at the north end of Detroit's Eastern Market, the last of the three public open-air markets that once served the citizens of Detroit. Along with the 1996 renovation of the Eastern Market came the desire to revitalize the surrounding areas as well. Rocky Peanut Company was one of the businesses that stepped up to the plate. Rocky Peanut Company has renovated more than 40,000 square feet of commercial space in Eastern Market, with Fire House #5 being its latest project.

At the time of its purchase in 1996, the 3,200-square-foot firehouse and its additions needed a complete renovation. The roof, in particular, presented a real challenge. Robert Heide, the project's leader explained, "We didn't have the original spec for the roof, but a picture from the 1930s led us to believe it was slate. Slate was out of the question for two reasons: cost and the new third floor design."

To address the cost issue, Bob Heide chose CertainTeed's Grand Manor Shingle® in Stonegate Gray. A heavyweight asphalt roofing shingle, Grand Manor looks like slate when installed. To accommodate the redesigned attic, the roof was raised 3 ½ inches, after which squares of Grand Manor Shingle® were laid. The team also installed CertainTeed's Carriage House Shingle™ on the dormer walls.


As the project rolled towards completion, the project leader looked towards the future, "These things take time, particularly as the market generates more interest and stakeholders. But I'm certain it can be done — one renovation at a time."

## NORTH KINGSTOWN TOWN HALL

**L**ocated on the western shore of the Narragansett Bay in Rhode Island, North Kingstown boasts several buildings that are listed on the National Register of Historic places. The North Kingstown Town Hall is one such recognized building. Most of the historic buildings in the town, including the Town Hall, were constructed around the turn-of-the-century, and were built with slate roofs. The age of these roofs, combined with the salt air and the local seagull activity, had taken their toll on the structures. The seagulls presented an unusual challenge; they used the roof as a resting place on which to crack open their clams. The consistent breaking of the shells, however, was wreaking havoc on the roof. It was time to replace the roof on the Town Hall.

Bob Canarri, Facilities Project Manager for North Kingstown, started looking for the right materials. Repairs could be made using slate and slate substitutes, but these materials were costly and might not hold up under the regions' freeze-thaw cycles and persistent seagulls.

When Canarri heard that a local lighthouse had used CertainTeed's Grand Manor Shingle®, he began to realize that he found the answer. Grand Manor Shingle® is a heavyweight asphalt roofing shingle that simulates slate. Because it features two full-size, one-piece base shingles, random 8-inch tabs, and shadow lines, Grand Manor provides the depth and dimension of slate, a requirement for a historic building. Once Canarri saw how Grand Manor performed on the lighthouse, he knew it would work for the Town Hall as well. However, fearing that that asphalt roof would compromise the historic value of the building, the Rhode Island Preservation and Heritage Commission was initially less enthusiastic.



Canarri knew that if the Commission members saw Grand Manor in action, their fears would disappear. He arranged for the Commission to travel with him to Milton, MA, where he showed them a home roofed in Grand Manor Stonegate Gray. The Commission agreed that Grand Manor provided a terrific placement for slate and looked so good on the Milton house, that they approved it for use on the Town Hall.

Canarri is pleased with how the project turned out, "Grand Manor exceeded our expectations. It cost less than slate and offered an outstanding warranty. And its rougher surface seems to be less appealing to the local seagulls."



In this late 19th century adaptation of Romanesque architecture, the patterned brick and bands of rough hewn stone were chosen to give an imposing as well as substantial appearance to the hall.


## THE SHILOH HOUSE

**R**everend John Alexander Dowie designed the roof on Shiloh House, his 1902 parsonage in Zion City, Illinois, to symbolize the Holy Spirit emanating from Zion. Citizens in Zion City wonder if the religious tribute offers heavenly protection to the building as well.

As 33 tornadoes whipped through north-eastern Illinois in April 1996, Tom Pierson of Precision Roofing, held his breath. Would the roof on Shiloh House survive the terrible storms? Thankfully, the answer was yes. Was it the CertainTeed shingle? Or John Alexander Dowie's tribute? "It depends on who you ask," maintains Pierson. "My guess is that it was a little of each." Pierson is a good one to ask because he's a lifelong resident of Zion.

Shortly after purchasing Shiloh House in 1967, Zion Historical Society selected Precision Roofing to reroof the building and to recreate the roof's original look and replicate its heritage.

Precision stripped off the entire roof. The entire deck was then covered with CertainTeed's WinterGuard™ Waterproofing Shingle Underlayment. The back of the roof is not visible from the street, so the team chose a standard three-tab fiber glass shingle for the roofing on the back. The front and east deck was roofed with CertainTeed's Carriage House Shingle™ in Sherwood Forest green. Carriage House was selected for its chamfered edges and deep shadow lines, which replicated the look of the original roof. The valleys were flashed with copper flashing, and the ridge was capped with Grand Manor Shingle®/Carriage House Shingle™ Accessory.




Restorers replicated Dowie's design and the look of the original roof with CertainTeed's Carriage House Shingle™ fiber glass shingles in Sherwood Forest Green, overlaid with individually cut Carriage House tabs in varying colors.

Pierson also used Carriage House to recreate Dowie's design on the roof. The roofers cut Black Pearl, Georgian Brick, and Heirloom Silver Carriage House Shingles into individual tabs and overlaid the design.

Exactly why the roof withstood the 1996 tornadoes is a matter for speculation. Of significance to Tom Pierson is that Shiloh House continues to display the traditions of his hometown.

## MALTA BOAT CLUB



These diamond-patterned window lights are original, and characteristic of the Victorian era.



Massive hand-carved brackets extend from the heavy masonry base to support the upper stories.

Most locals consider Boathouse Row, a National Historic Landmark, the true “skyline” of Philadelphia. Running parallel to the Schuylkill River, Boathouse Row encompasses thirteen rowing club buildings, including the Malta Boathouse, and hosts numerous national regattas.

Founded in 1860, the club’s first regular racing crew competed in the Schuylkill Navy Regatta in a six-oared boat, *Intrepid*, five years later. The Malta Boat Club has a long, successful history of competitive rowing, winning its first National Championship in 1924.

In 1865, Malta purchased the Excelsior Club on the present site of the Malta Boat Club. In 1902, the boathouse was expanded to its current size based on a design by architect George W. Hewitt. Characteristic of the Victorian era, the building is distinguished by its hand-carved, scalloped rake boards and cedar siding.

In 1993, a total exterior renovation took place. An inexpensive asphalt roof was removed and replaced by Grand Manor Shingle® in Stonegate Gray. Remarks Anthony Weber, architect and club member, “As the largest building on Boathouse Row, and with a prominent roof, we considered slate but our budget didn’t allow it. Synthetic slates didn’t have the quality we wanted. Grand Manor looks like individual slate, creates depth and is visually rich, and carries an exceptional warranty.”

CertainTeed shingles can also be found on Vesper, which adjoins Malta. Decades ago, Vesper installed Hallmark Shingle, a shingle with the look of hand-split wood shakes. During a recent exterior renovation, they again chose CertainTeed, this time selecting Carriage House Shingle.™

## THE FAIRVIEW GERMAN BILINGUAL SCHOOL


When the Fairview School opened in 1888, its curriculum included instruction in the German language, an offering that embraced and continued the strong German traditions of Cincinnati, Ohio. Classes in German were discontinued with the advent of World War I.

By the early 1970s, Cincinnati developed an alternative school program to promote desegregation and offer parents more educational choices for their children. In 1974, Fairview School once again offered German on a limited basis, and in so doing, became part of the first program in the United States to offer primary students intensive second-language instruction. By 1978, Fairview closed as a neighborhood school to become an alternative school only. The school's consistently high standards of academic achievement earned it recognition from the National Department of Education in 1986.

A testament to the Romanesque Revival style, Fairview's notable architectural features include an imposing roofline, repetitive geometric elements, arched entryways and numerous windows.

When the original slate roof needed replacement, the school board first selected natural slate, a choice it subsequently found unaffordable, then Grand Manor Shingle® in Stonegate Gray. The results were impressive: On viewing the new asphalt shingle roof, some school board members actually thought that natural slate had been used mistakenly!

At approximately 45% less cost than slate, Grand Manor helps protect this educational hallmark and preserves the aesthetics of the original structure — an excellent lesson in any language.



A pair of Palladian windows graces the third floor of the Romanesque Revival school. Heavy overhead arches accentuate the lines for a dramatic touch.

## SOURCES AND PUBLICATIONS

National Trust for Historic Preservation  
1785 Massachusetts Avenue, N.W.  
Washington, D.C.  
(202) 588-6000

The only private, non-profit organization chartered by Congress to encourage the public to preserve sites, buildings and objects significant in American culture and history. Membership includes a subscription to the bi-monthly magazine, *Historic Preservation*.

### *Federal Historic Preservation Laws*

A brochure by the U.S. Department of the Interior on legislature concerning National Historic Preservation programs, National Historic Landmarks, Federal Preservation Tax Incentives and more. Available through the U.S. Government Printing Office, Washington, D.C., (202) 512-1800.

### *Preservation Briefs*

#4: *Roofing for Historic Buildings*, S.M. Sweetser, 1978. Published by the U.S. Department of the Interior, this brief discusses alternative roofing materials, among other topics.

### *Technology & Conservation*

A magazine for the analysis, preservation, restoration, protection and documentation of art, architecture and antiques.

### *Old-House Journal*

A practical bi-monthly magazine for homeowners interested in renovating old homes.

## SUGGESTIONS FOR HISTORIC RENOVATORS

- ☐ Call your city government to obtain guidelines for historic renovation. Determine if your renovations and materials must be approved by a local review board.
- ☐ Contact your State Historic Preservation Office for additional information, guidelines and resources.
- ☐ Maintain comprehensive files on the history of your home or building, including all historic certifications, photographs and drawings.
- ☐ Prepare a document detailing the proposed renovations. Include materials of construction, past and proposed. Obtain information from the manufacturers for any alternative materials.
- ☐ If your renovations are substantial, consult with historic renovation specialists or architects. An invaluable resource, they can also support you at any hearings and provide information on possible tax incentives.

## N O T E S



THE HENRY FORD HOUSE  
Detroit, Michigan  
*Built in 1908*  
Fasten Right Roofing, Inc.,  
Roofing Contractor.  
Grand Manor Shangle® in  
Sherwood Forest, 78 Squares.  
Registered Michigan Historic  
Site, 1990.



SHILOH HOUSE  
Zion City, Illinois  
*Built in 1902*  
Precision Roofing, Inc., Contractor.  
Carriage House Shangle™ in  
Sherwood Forest, 25 Squares.  
Listed with the Zion Historical  
Society, 1967.



THE MONTPELIER WHITE HOUSE  
Montpelier, Ohio  
*Built in 1877*  
Gray's Construction Company,  
Contractor.  
Carriage House Shangle™ in  
Sherwood Forest, 21 Squares.  
Application submitted, National  
Register of Historic Places.



NORTH KINGSTOWN TOWN HALL  
North Kingstown, Rhode Island  
*Built in 1890*  
Pezzucchi Construction Company,  
Contractor.  
Grand Manor Shangle® in  
Stonegate Gray, 50 Squares.  
Listed on the National Register  
of Historic Places.



THE ROMEO HOUSE  
Romeo, Michigan  
*Built in 1871*  
A & G Properties, Inc., Contractor.  
Grand Manor Shangle® in  
Brownstone, 32 Squares.  
Listed with the Romeo Historic  
Society, 1994.



THE FAIRVIEW GERMAN  
BILINGUAL SCHOOL  
Cincinnati, Ohio  
*Built in 1888*  
SFA Architects, Project Architect.  
Imbus Roofing, Roofing Contractor.  
Grand Manor Shangle® in  
Stonegate Gray, 230 Squares.



ORCHARD STREET CHURCH  
Headquarters for the Baltimore  
Urban League  
Baltimore, Maryland  
*Built in 1883*  
Kelly, Clayton & Mojzisek,  
Architects, Project Architect.  
Struener Bros., Eccles & Rotuse, Inc.,  
General Contractor.  
Grand Manor Shangle® in  
Stately Black®, 100 Squares.  
Listed on the National Register  
of Historic Places, 1975.



MALTA BOAT HOUSE  
Philadelphia, Pennsylvania  
*Built in 1883*  
Anthony Weber Architects,  
Project Architect.  
Gardner-Fox Associates,  
General Contractor.  
Grand Manor Shangle® in  
Stonegate Gray, 60 Squares.  
Listed on the National Register  
of Historic Places, 1987.  
Declared a National Historic  
Landmark, 1987.



DETROIT FIRE HOUSE No. 5  
Detroit, Michigan  
*Built in 1888*  
Detroit Cornice and Slate,  
Contractor.  
Grand Manor Shangle® in  
Stonegate Gray, 65 Squares.  
Listed on the National Register  
of Historic Places.

## St. Mary's Commons Apartments Roof Replacement Project Bid Results Spreadsheet

Bid Date - October 5, 2023

|                                                              | Contractor "A"  | Contractor "B"  | Contractor "C"  | Contractor "D"  | Contractor "E"  | Contractor "F"  | Contractor "G"  |
|--------------------------------------------------------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| Base Bid #1<br>Slate                                         | \$ 3,144,000.00 | \$ 3,085,251.00 | \$ 3,290,327.00 | \$ 4,548,000.00 | No Bid          | \$ 3,175,970.00 | No Bid          |
| Base Bid #2<br>Synthetic Slate                               | \$ 2,950,000.00 | \$ 2,902,492.00 | \$ 2,945,782.00 | \$ 4,203,000.00 | No Bid          | \$ 2,715,970.00 | \$ 1,675,000.00 |
| Base Bid #3<br>Shingles (Grand Manor)                        | \$ 2,540,000.00 | \$ 2,401,322.00 | \$ 2,451,000.00 | \$ 3,792,000.00 | \$ 1,978,866.00 | \$ 1,878,970.00 | \$ 1,395,000.00 |
| Unit Price #1<br>Replace exist. wood deck<br>Per Square Foot | \$ 28.00        | \$ 17.40        | \$ 50.00        | \$ 24.00        | \$ 12.00        | \$ 18.50        | No Bid          |
| Unit Price #2<br>Hourly labor rate<br>Per Hour               | \$ 85.00        | \$ 87.00        | \$ 98.50        | \$ 128.00       | \$ 85.00        | \$ 79.50        | \$ 95.00        |
| Completion                                                   | 365 days        | 240 days        | 180 days        | Varies by Bid   | TBD             | 150 days        | TBD             |
| Start Date                                                   | Spring 2025     | March 4, 2024   | TBD             | March 2024      | Spring 2024     | TBD             | TBD             |

**THE BROWNE COMPANY**  
*Roofing and Waterproofing Consultants, Inc.*  
 98 Forest Drive  
 Orchard Park, New York 14127  
 Phone/Fax (716) 667-0802  
 email: browneco@verizon.net

December 4, 2023

Mr. James Quinn  
 Town of Amherst Historic Preservation Committee  
 5583 Main Street  
 Williamsville, NY 14221

Reference: St. Mary's Common Apartments Roof Project  
 Town of Amherst Historic Preservation Committee  
 Application for Certificate of Appropriateness  
 Architectural Review

Dear Mr. Quinn

In October, as per the Committee's request, we solicited bids for roof replacement work at St. Mary's Common Apartments for three different roof systems: slate, synthetic slate, and a high-end architectural shingle. We received bids from seven different roofing contractors. We've chosen to go with Besroi Roofing's Base Bid No. 2 for a synthetic slate shingle roof system. It is about half the price of the slate bids we received.

Besroi is a certified WBE (Women owned business enterprise), they have been in business for over 60 years, and they are very familiar with the specifics of this project. They have experience installing synthetic slate roof systems as well as high-end architectural shingles.

The Ownership group of St. Mary's Common Apartments would like to use an EcoStar Synthetic Slate, first color choice is "Napa Blend"; second color choice is "Scottish Blend." Please see page 20 of the attached manufacturer's literature from EcoStar.

Besroi would like to start as early as possible in the Spring, probably around April 1, 2024, with completion in 180 calendar days (weather depending.)

Please feel free to contact me if you have any questions concerning this information.

Sincerely

THE BROWNE COMPANY

*Gary Browne*

Gary Browne, IIBEC, CSI, CDT  
 Roof Consultant

Attachment: 12-04-23 Letter to Amherst Historic Preservation Committee (28304 : St. Mary's)



EcoStar LLC  
42 Edgewood Drive  
Holland, NY 14080  
800.211.7170  
EcoStarLLC.com

Find us on social media:



# Synthetic Slate & Shake Roofing

Durable, sustainable  
building product



Made with recycled  
polymer and rubber  
(not tires)



Less than half the  
weight of natural slate



Class C and Class A  
fire ratings available



Class 4 hail impact  
resistance rating



50-year transferable  
warranty available

Design Your Roof,  
Your Way



www.ecostarllc.com



Majestic Niagara Slate 12" in Stormy Gray Blend



Highly Sustainable | Highest Testing Performance | Proven Longevity | Uncompromised Beauty

Proudly Made in the USA

Packet Pg. 109



Thank you for your interest in EcoStar

For 30 years, EcoStar has been a pioneer in the synthetic slate and shake roofing markets. We pride ourselves in making products that turn everyday steep-slope roofs into extraordinary extensions of our customers' visions. Our team has long been in place ensuring all our products perform at the highest level. We have followed a stringent quality program since 1997 and are audited every 6 months in accordance with ISO 9001, UL and other certification agencies.

EcoStar is dedicated to helping the world address recyclable materials. Since 1993, we have redirected thousands of tons of valuable raw materials away from landfills each year. By using post-industrial upcycled materials, EcoStar tiles aid in the preservation of natural resources. No trees are cut down and no slates are quarried for the manufacture of EcoStar products.

EcoStar is here for you. If you have a vision for your roof, we can turn it into reality. And you can rest assured that the beauty of your roof will last as long as you call it home.

Why Choose EcoStar?

- Highly Sustainable
- Designed to Perform
- Highest Testing Performance
- Largest Profile Offering
- Unmatched Weathering Capability
- Color Match Excellence
- Proven Longevity
- Easy Installation
- Uncompromised Beauty
- Made in the USA



Contents

|    |                                                                                              |
|----|----------------------------------------------------------------------------------------------|
| 2  | The EcoStar Difference                                                                       |
| 4  | Traditional Slate                                                                            |
| 6  | Niagara Slate                                                                                |
| 8  | Random-Width Blends                                                                          |
| 10 | Features and Benefits:<br>Majestic Slate, Empire Slate and Niagara Slate                     |
| 12 | Traditional Shake                                                                            |
| 14 | Aspen Blend                                                                                  |
| 16 | Niagara Shake                                                                                |
| 18 | Features and Benefits:<br>Seneca Shake, Empire Shake, Empire Shake Plus<br>and Niagara Shake |
| 20 | Color Options                                                                                |
| 22 | Commercial and Historic Applications                                                         |
| 24 | Installation and Accessories                                                                 |
| 25 | Complete Warranty Protection & Custom Projects                                               |

"This is our second project using EcoStar Majestic Slate and our crews love the ease of installation and our customers love the distinctive look on their roofs."

- Alan Frank, Alan Frank Roofing Co.



## The EcoStar Difference

*As the leading manufacturer of sustainable roofing tiles, we recognize the challenges our world faces regarding Earth's limited resources, non-renewable energy sources, and responsible disposition of waste.*

EcoStar LLC leads the composite steep-slope roofing industry with its premium synthetic slate and shake roofing tiles. EcoStar products are made to the highest of standards and are the environmentally-responsible choice for contractors, specifiers, architects and property owners. EcoStar tiles are manufactured in the USA with a material made of up to 80% upcycled post-industrial rubber and plastic.

Over the years, technology has enhanced our already exceptional weathering performance. Product weathering occurs in all synthetic roofing products regardless of material content (recycled or virgin). Our lot control methods ensure that our tiles weather uniformly, so that over time, EcoStar tiles lose their slight sheen and develop a patina, continuing the replication of their natural counterparts. Testing our products remains paramount to providing products that look beautiful and realistic when first installed, and even more natural with each year of exposure to mother nature. In other words, we improve with age!

*Manufactured in strict adherence to ISO 9001 Quality Management Standards.*



EcoStar LLC—pioneers of sustainable roofing since 1993.



1.e

Attachment: 12-04-23 Letter to Amherst Historic Preservation Committee (28304 : St. Mary's)

### upcycle

*transitive verb*

: to recycle (something) in such a way that the resulting product is of a higher value than the original item : to create an object of greater value from a discarded object of lesser value.



**20-Year Old Roof**  
Majestic Slate 12" in  
Midnight Gray

# Traditional Slate


## The enduring beauty of slate.

An affordable and environmentally friendly alternative to natural slate, our Traditional Slate lines of recycled roof tiles capture the beauty of natural slate. Traditional Slate is available in single widths (10" and 12"), Designer Tiles (Beveled Edge, Chisel Point and Beaver Tail) and a Random-Width Blend (6", 9" and 12").

Featured image: Majestic Slate 12" in Federal Gray



From left to right: Majestic Slate Beaver Tail in Midnight Gray, Mountain Plum and Chestnut Brown; Majestic Slate 12" in Chestnut Brown; Majestic Slate 12" in Twilight Blend



Featured tiles: Majestic Slate 12" in Smoke Gray, Federal Gray and Stone Red



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Niagara Slate

The thickest, most natural-looking slate profile.

Bigger is better when it comes to Niagara Slate, EcoStar's largest profile slate, designed to create enhanced shadow lines for maximum aesthetic appeal. Niagara Slate is available in single widths (10", 12" and 14") and a Random-Width Blend.

Featured image: Majestic Niagara Slate 14" in Chestnut Brown



From left to right: Majestic Niagara Slate 12" in Stormy Gray Blend; Majestic Niagara Slate 14" in Chestnut Brown; Majestic Niagara Slate 12" in Midnight Gray



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



Featured tiles:  
Majestic Niagara Slate in Federal Gray, Mountain Plum and Smoke Gray

# Random-Width Blends

## The most realistic slate blends.

Random-Width Blends are available in both Traditional and Niagara product lines. Traditional Random-Width Blend includes 6", 9" and 12" Majestic Slate or Empire Slate tiles. Niagara Random-Width Blend includes 10", 12" and 14" Majestic Niagara Slate or Empire Niagara Slate tiles. An even number of each size tile is included in every bundle for ease of installation on-site. With straight and staggered installation options, these blends provide the look you desire and the protection you need.

Featured image: Majestic Niagara Slate Random-Width Blend in Black



From left to right: Majestic Slate Random-Width Blend in Earth Green; Majestic Niagara Slate Random-Width Blend in Black; Majestic Niagara Slate 14" and 12" Blend in Black



Featured tiles: Majestic Slate Random-Width Blend in Midnight Gray



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Innovative Design, Classic Slate Look


## EcoStar Slate

Post-industrial recycled compounds are utilized to create a lightweight and environmentally responsible alternative to natural slate. An EcoStar roof offers beautiful, yet proven protection for your most prized investment. It is an inspiration to homeowners looking for affordable style and uncompromised performance.


### Significant advantages:

- Weighs significantly less than natural slate
- Protects against extreme weather conditions
- Reduces need for maintenance and repair
- Lessens environmental impact
- Exceeds industry performance standards
- 50-year warranty

### Profiles



### Majestic Standard Colors



Color samples may not accurately represent the true color level or variations of color blends that will appear on the roof. Colors and specifications subject to change without notice. EcoStar is not liable for color variations or shading.



Looking for a more unique look?  
Achieve a custom look by combining multiple profiles and/or colors. See page 20 to learn more.

All EcoStar products are factory pre-blended for both color and width.

## The right tile for any property

Whether you are looking to elevate the look of a residential property, meet the performance needs of a commercial property, or preserve the look of a historical property, EcoStar offers the right tile.

### Majestic Slate

EcoStar's original eco-friendly tile, made of 80% recycled materials, meeting the needs of most residential applications.

### Empire Slate

The same classic slate look as Majestic Slate with additional energy-saving benefits, and design features that meet the needs of commercial and historical properties.

### Niagara Slate

Niagara Slate is available in the Majestic and Empire formulas and offers an increased tile size and thickness for enhanced shadow lines and increased aesthetic appeal.


Our slates replicate real slate in so many ways - the beauty and durability, the slight sheen after installation, and the gentle patina of the surface over time.

| Tile Features                         | Majestic Slate      |                     | Empire Slate        |                     |
|---------------------------------------|---------------------|---------------------|---------------------|---------------------|
|                                       | Traditional         | Niagara             | Traditional         | Niagara             |
| Recycled Material                     | 80%                 | 80%                 | 25%                 | 25%                 |
| Tile Widths                           | 12", 10", 9", 6"    | 14", 12", 10"       | 12", 10", 9", 6"    | 14", 12", 10"       |
| Profile                               | Solid               | Cavity-back         | Solid               | Cavity-back         |
| Tile Thickness                        | 1/4"                | 5/8"                | 1/4"                | 5/8"                |
| Reveal                                | 7", 6"              | 10", 9"             | 8", 7", 6"          | 10", 9"             |
| Weight per Square (at maximum reveal) | 275 lbs. (12" tile) | 250 lbs. (14" tile) | 308 lbs. (12" tile) | 290 lbs. (14" tile) |
| Fire Rating                           | Class C             | Class C             | Class C/A           | Class C/A           |
| Impact Rating                         | Class 4             | Class 4             | Class 4             | Class 4             |
| Miami-Dade                            | No                  | No                  | Yes                 | Yes                 |
| Standard Colors                       | 12                  | 12                  | 14                  | 14                  |
| Cool Roof Colors                      | No                  | No                  | 11                  | 11                  |
| Custom/Marbled Colors                 | No                  | No                  | Yes                 | Yes                 |
| Designer Tiles                        | Yes                 | No                  | Yes                 | No                  |

### Cool Colors

Enjoy additional energy savings from our line of Cool Colors, available in all Empire colors. (excludes Bedford Black, Tioga Terra Cotta and Plymouth Patina)

### Empire Standard & Cool Colors



"EcoStar synthetic slate was just what we were looking for. We were able to select the size, shape, and blend of colors required to give our home the look of a well-preserved nineteenth-century structure."

- Jay Panzer, Homeowner

EcoStar representatives are available for information about energy savings and homeowners insurance discounts. Visit our website to find your local representative.

# Traditional Shake

The enduring beauty of shake.

EcoStar's Seneca Shake, Empire Shake and Empire Shake Plus tiles create the look of authentic hand-split wood shake. They provide protection from fire, resistance to the elements, potential property insurance cost reductions and require little-to-no maintenance.

Featured image: Seneca Shake in Black



From left to right: Seneca Shake in Mountain Plum; Seneca Shake in Black; Empire Shake in Hampton Harbour



Featured tiles: Seneca Shake in Sage Green, Cedar Brown and Stone Red



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Aspen Blend

The most realistic shake blend.

Aspen Blend replicates the look of thick, hand-split wood by using a combination of Empire Shake and Empire Shake Plus tiles. This blend is manufactured in random widths of 6", 9" and 12" and thicknesses of 3/8" and 3/4" for the rich, traditional look of wood shake.

Featured image: Aspen Blend in Hampton Harbour



From left to right: Aspen Blend in Driftwood; Aspen Blend in Feathered Driftwood; Aspen Blend in Cedar Brown



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



Featured tiles: Aspen Blend in Driftwood and Hampton Harbour

# Niagara Shake

The thickest, most natural-looking shake profile.

Bigger is better when it comes to Niagara Shake, EcoStar's largest profile shake that was designed to create enhanced shadow lines for maximum aesthetic appeal.

Featured image: Majestic Niagara Shake in Chestnut Brown



From left to right: Empire Niagara Shake in Hampton Harbour; Majestic Niagara Shake in Chestnut Brown; Empire Niagara Shake in Manhattan Midnight



Featured tiles:  
Empire Niagara Shake in Hampton Harbour



Discover more design ideas in our online photo gallery by scanning the QR code or visiting [ecostarllc.com](http://ecostarllc.com).



# Sustainable Design, Hand-crafted Appeal

## EcoStar Shake

EcoStar shake tiles replicate the look of natural hand-split cedar shakes. The tile molds have been custom crafted using real wood shake tiles as a template to create an intricate texture that appears truly natural. Compare EcoStar shake to any other synthetic shake product and you will see the difference.

### Significant advantages:

- Reduced maintenance and repairs
- Longer life
- Exceeds industry performance standards
- Mold and algae resistant
- Resistant to weathering, rot and cracking
- Reduced environmental impact
- Available in multiple colors, sizes and thicknesses
- 50-year warranty

### Tile blends for a natural look

Our **Standard Blend** uses a mixture of all three widths of Seneca Shake or Empire Shake. For an even greater visual impact, **Aspen Blend** includes 2/3 Empire Shake (3/8" thick) and 1/3 Empire Shake Plus (3/4" thick) in all three widths.




**Standard Blend**  
Mixture of Seneca Shake or Empire Shake in all three widths.



**Aspen Blend**  
Combines 2/3 Empire Shake (3/8" butt) and 1/3 Empire Shake Plus (3/4" butt) in all three widths.

### Seneca / Majestic Standard Colors



## The right tile for any property

Whether you are looking to elevate the look of a residential property, meet the performance needs of a commercial property, or preserve the look of a historical property, EcoStar offers the right tile.

### Seneca Shake

EcoStar's original synthetic shake tile, meeting the needs of most residential roofing and siding applications, and made of 80% recycled material.

### Empire Shake Plus

All the benefits of Empire Shake with a 3/4" thickness for even greater aesthetic appeal.

### Niagara Shake

Niagara Shake is available in the Majestic and Empire formulas and offers an increased tile size and thickness for enhanced shadow lines and aesthetic appeal.

### Empire Shake


The same classic shake look with additional energy-saving benefits and design features that meet the needs of commercial and historical properties.

| Tile Features                         | Seneca/Majestic   |                       | Empire            |                   |                       |
|---------------------------------------|-------------------|-----------------------|-------------------|-------------------|-----------------------|
|                                       | Shake             | Niagara               | Shake             | Shake Plus        | Niagara               |
| Recycled Material                     | 80%               | 80%                   | 25%               | 25%               | 25%                   |
| Tile Widths                           | 12", 9", 6" blend | 10", 9", 8", 7" blend | 12", 9", 6" blend | 12", 9", 6" blend | 10", 9", 8", 7" blend |
| Profile                               | Solid             | Cavity-back           | Solid             | Cavity-back       | Cavity-back           |
| Tile Thickness                        | 3/8"              | 3/4"                  | 3/8"              | 3/4"              | 3/4"                  |
| Reveal                                | 8", 7"            | 10", 9"               | 9", 8", 7"        | 9", 8", 7"        | 10", 9"               |
| Weight per Square (at maximum reveal) | 261 lbs.          | 216 lbs.              | 277 lbs.          | 371 lbs.          | 250 lbs.              |
| Fire Rating                           | Class C           | Class C               | Class C/A         | Class C/A         | Class C/A             |
| Impact Rating                         | Class 4           | Class 4               | Class 4           | Class 4           | Class 4               |
| Miami-Dade                            | No                | No                    | Yes               | Yes               | Yes                   |
| Standard Colors                       | 12                | 12                    | 14                | 14                | 14                    |
| Cool Roof Colors                      | No                | No                    | 11                | 11                | 11                    |
| Custom/Marbled Colors                 | No                | No                    | Yes               | Yes               | Yes                   |

### Cool Colors

Enjoy additional energy savings from our line of Cool Colors, available in all Empire colors. (excludes Bedford Black, Tioga Terra Cotta and Plymouth Patina)

### Empire Standard & Cool Colors



Color samples may not accurately represent the true color level or variations of color blends that will appear on the roof. Colors and specifications subject to change without notice. EcoStar is not liable for color variations or shading.



### Want to customize your curb appeal?

Give the visual impact your property deserves by choosing a combination of colors or by developing a custom color. See page 20 to learn more.

All EcoStar products are factory pre-blended for both color and width.

"It's not only the most aesthetically pleasing roofing system I've seen, but the durability and value is not comparable to any other product."

- Justin Diliberto, Divine Residential LLC

EcoStar representatives are available for information about energy savings and homeowners insurance discounts. Visit our website to find your local representative.

# Color Options to Fit Your Style


## Factory Blends\*

EcoStar provides unlimited potential to enhance the beauty of your property with the option of color blends - available in all product lines. From "Wide-Range" blends, which include multiple shades of the same color, to completely custom multi-color mixes, you can create a striking roof with unique style.

### Slate Color Blends:




Scottish Blend




Tuscan Blend




Napa Blend



Summit Blend



Wood Trail Blend




Sierra Blend

### Shake Color Blends:

### Wide Range Blends:




Stormy Gray Blend



Twilight Blend



Forest Blend



Canyon Blend

## Marbled Blends

EcoStar offers eight beautiful marbled blends in our Empire product lines. Each blend contains a minimum of 2-3 different marbled tiles offering a unique look for any project. Our marbled blends are also available in solid colors. Ask your representative for more details.



Riverbed



Vineyard




Rolling Meadow




Harvest Hill




Ancient Quarry



Feathered Driftwood



Fresh Cut Cedar



Hunters Creek Blend



## Custom Colors

EcoStar's production team can create slate and shake tiles with unique hues based on samples of material, paint swatches, or Pantone® color numbers that highlight your property. Design ideas for your project are endless.



Majestic Niagara Slate 12" in Stormy Gray Blend

*\* All EcoStar products are factory pre-blended for both color and width.*

*"EcoStar is the cream of the crop. From the people who produce it, to the product, and right down to the installation. It's a product made from recycled material with an authentic look, backed by one of the best warranties in the industry."*

**- Ronald Cole, The Roof Connection**



Top: Empire Slate 12" in Ancient Quarry

Bottom: Aspen Blend in Fresh Cut Cedar

# Commercial and Historic Applications

## Exceeding the demands of commercial properties

As a pioneer of synthetic roofing products since 1993, EcoStar has become a favorite for educational buildings, religious facilities and government projects. Designed with up to 6" headlap for installation integrity, EcoStar roof systems exceed best practice roofing techniques, ensuring the longevity of your roof. All EcoStar products are manufactured under strict adherence to ISO 9001 quality management standards.

## Preservation meets conservation

EcoStar products allow preservationists to match the distinctive look of an original roof while meeting modern day performance expectations, limiting the use of natural resources, reducing waste and minimizing carbon footprint. Focusing on reducing, reusing and recycling promotes the lasting benefits of conservation while allowing us to protect our cultural heritage. EcoStar tiles offer flexible installations, such as staggered and offset, to better match original roof designs. EcoStar has been approved for use in historic preservation projects throughout the United States.

## Features and benefits:

- Weighs significantly less than natural slate
- Requires little-to-no maintenance
- Offers energy-saving cool colors
- Includes up to 80% post-industrial recycled content
- Easy application keeps installation costs down
- May contribute toward LEED certification
- Available in a wide variety of profiles and colors
- 50-year warranty is standard

*Majestic Slate has been widely accepted by preservationists and historians for nearly 30 years.*



Top (Right): Majestic Slate 12" in Stone Red

Bottom: Empire Slate Beveled Edge in Manhattan Midnight Wide Range and Freeport Federal Wide Range

*"Our large, historic home had a very old, deteriorating, and unsightly slate roof that needed frequent repairs. Our new EcoStar Majestic Niagara Slate roof matches the original roof perfectly and restores our home to its former beauty."*  
- **David M., Homeowner**

*"We are so pleased with the look and performance of the roofing."*

- **Bill Ingram, Land Management, Inc.**



Bottom (Left to Right): Majestic Niagara Slate in Sage Green, Cedar Brown and Mountain

Majestic Slate 12" in Midnight Gray and B

Majestic Niagara Slate 12" in Smoke Gray, Federal Gray, Midnight Gray, and Mountain



# Installation and Accessories

EcoStar's extensive network of Gold Star Applicators have been professionally trained to provide you with a remarkably beautiful installation. Our accessories are designed to complement EcoStar synthetic roofing tiles, and are proven to extend the longevity of a roofing system.

*Our reliable protection encompasses every component of the EcoStar roof installation.*



## Glacier Guard

Glacier Guard is an impermeable self-adhering membrane, offering enhanced protection against moisture penetration. A high-temperature self-adhered membrane is also offered.



## Aqua Guard

Aqua Guard is a versatile roofing underlayment offering a stronger and lighter alternative to traditional felt.



## Ridge Vent

EcoStar offers a continuous tile-over ridge vent that efficiently removes moisture build-up in the attic space of a building.



## EcoStar Fasteners

Our stainless steel fasteners provide superior strength and resistance to corrosion, staining and leaking.

# Complete Warranty Protection

A standard 50-year Limited Material Warranty is offered at no extra charge with the purchase of an EcoStar roof. To ensure that your EcoStar roof will perform at its best, consider the benefits of our transferable 50-Year Gold Star Limited Labor and Material Warranty.

## Standard Warranty

Non-Transferable, Limited Materials

## Gold Star Warranty

Transferable, Limited Labor and Materials

EcoStar representatives are available for information about energy savings and homeowners insurance discounts. Visit our website to find your local representative.

# Custom Projects

Whether you're looking for a custom color or shape, EcoStar has the in-house capability to develop a solution for your unique project.



Island Groove Clay Tile




Saw Cut Tile



Fish Scale Tile

Call us today at **800.211.7170** or visit **[www.ecostarllc.com](http://www.ecostarllc.com)** for more information.



1.e

Attachment: 12-04-23 Letter to Amherst Historic Preservation Committee (28304 : St. Mary's)



A roof that is just as reliable as beautiful; the result of opting for our Gold Star Certified Applicators at every installation.

## Protection Overview

- Miami Dade prolonged and accelerated weathering @ 4,500 hours
- Job lot control produces uniform roof tile weathering
- Miami Dade Wind TAS100 & TAS125 (NOA # 17\_1227\_10)
- UL listed Class C or A fire resistance (UL 790)
- UL Class 4 (highest rating) hail impact resistance (UL 2218)
- ISO 9001:2015 Quality Management Standards
- 50-Year Material Warranty
- 50-Year Transferable Labor and Material Warranty available

Proudly approved and certified by the following organizations:



Underwriters Laboratories (UL)®

Texas Department of Insurance

Florida Building Code

Visit [www.ecostarllc.com](http://www.ecostarllc.com) for a complete listing of approvals and certifications.



Top: Majestic Slate 12" in Federal Gray

Bottom: Aspen Blend in Midnight Gray

## HISTORIC PRESERVATION COMMISSION

### DRAFT MEETING SCHEDULE – 2024

All meetings to begin at 7:00 p.m.

January 9

February 13

March 12

April 9

May 14

June 11

*No July meeting*

August 13

September 10

October 8

November 12

December 10

Attachment: 2024 Meeting Dates - Draft (28305 : 2024 Meeting Schedule)



Franklin Bronze Plaques  
4201 US 322 West  
Franklin PA 16323

## Quote/Order Acknowledgement

| Date      | Job No. |
|-----------|---------|
| 12/8/2023 | 34663   |

Vendor No. 20015

**Billing Address**

Town of Amherst  
5583 Main Street  
Williamsville NY 14221

**Ship To**

Town of Amherst  
5583 Main Street  
Williamsville, NY 14221

| Contact Person<br>Susan Palmer                                                                                                                                                                                                                                                                                                                                                                               |                         | E-mail Address                             |                  | Phone No.                                |        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------|------------------|------------------------------------------|--------|
| P.O. No.<br>QUOTE                                                                                                                                                                                                                                                                                                                                                                                            | Prev. Job #<br>TEMPLATE | Terms<br>Net 30                            | Must Have        | Ship Date                                |        |
| Description                                                                                                                                                                                                                                                                                                                                                                                                  | Qty                     | Background                                 | Mount            | Amount                                   | Total  |
| 12" x 8.5" Custom Bronze Plaque drilled and tapped for individual designation<br>*Historic Landmark                                                                                                                                                                                                                                                                                                          | 2                       | Dark Oxide                                 | Woodscrews       | 290.00                                   | 580.00 |
| 6" x 3" Historic Landmark Designation<br>*Text to be Determined                                                                                                                                                                                                                                                                                                                                              | 2                       | Dark Oxide                                 | Front / Template | 117.00                                   | 234.00 |
| Subtotal                                                                                                                                                                                                                                                                                                                                                                                                     |                         |                                            |                  |                                          | 814.00 |
| 10% Materials Surcharge                                                                                                                                                                                                                                                                                                                                                                                      |                         |                                            |                  | 10.00%                                   | 81.40  |
| Shipping and Handling                                                                                                                                                                                                                                                                                                                                                                                        |                         |                                            |                  | 60.00                                    | 60.00  |
| (LEATHERETTE)                                                                                                                                                                                                                                                                                                                                                                                                |                         |                                            |                  |                                          |        |
| Standard production is approximately 5 - 7 weeks after final layout approval and receipt of payment, plus time in transit for UPS, depending on the size and complexity of the plaque                                                                                                                                                                                                                        |                         |                                            |                  |                                          |        |
| <b><u>Please review details carefully and advise of any necessary corrections. Full text will be shown in the layout file when sent for review / revision / approval. Customer is responsible for any errors that are approved.</u></b><br><br><b><u>Due to the volatility of the copper market, estimates are valid for 30 days after issue date and are subject to requote after that time period.</u></b> |                         |                                            |                  | <b>Subtotal</b> \$955.40                 |        |
|                                                                                                                                                                                                                                                                                                                                                                                                              |                         |                                            |                  | <b>Sales Tax (0.0%)</b> \$0.00           |        |
|                                                                                                                                                                                                                                                                                                                                                                                                              |                         |                                            |                  | <b>Total</b> \$955.40                    |        |
|                                                                                                                                                                                                                                                                                                                                                                                                              |                         |                                            |                  |                                          |        |
| Phone #<br>814-346-7205                                                                                                                                                                                                                                                                                                                                                                                      | Fax #<br>814-346-7047   | E-mail<br>audrey@franklinbronzeplaques.com |                  | Web Site<br>www.franklinbronzeplaques.co |        |

Attachment: Plaque order invoice\_1 (28306 : 2023 Budget)



## Municipal Memberships

Local Historic Preservation Commissions (HPCs) play a pivotal role in promoting good stewardship and active use of historic properties in our community. And as such, it is critical for HPCs to regularly undergo training opportunities to ensure that Commissioners, local elected officials, and municipal staff have the preservation knowledge and tools needed to appropriately plan for and manage their community's historic built environment.

In recognition of the important role that our local municipalities play in advancing historic preservation, Preservation Buffalo Niagara (PBN) is now offering annual municipal memberships. Available at the Protector Circle level (\$250) or higher, municipal membership levels provide a variety of benefits tailored to the needs of HPCs.

If you have any questions about PBN's municipal membership program, please contact Christiana Limniatis, Director of Preservation Services, at 716-852-3300 or [climniatis@pbnsaves.org](mailto:climniatis@pbnsaves.org).

### Municipal Membership Levels

HPCs and their municipalities are welcome to join at any level that they are financially comfortable, but with memberships at the Protector Circle level (\$250) or higher, municipalities have access to a variety of special benefits:

#### Protector Circle (\$250):

- One (1) complementary session of "Preservation Commission 101." This workshop addresses the critical concepts, terminology, and preservation principles that commissioners need to successfully serve in their position.
- One (1) custom created educational programming. This program could be lecture/workshop geared for the public, or an HPC training sessions.
- Listing on our website and annual report as municipal members.
- Printed quarterly newsletter and weekly PBN e-update.

#### Conservator Circle (\$500):

- One (1) complementary session of "Preservation Commission 101."
- Two (2) custom created educational programming.
- Listing on our website and annual report as municipal members.
- Printed quarterly newsletter and weekly PBN e-update.

#### Steward Circle (\$1000):

- One (1) complementary session of "Preservation Commission 101."
- Three (3) custom created educational programming.
- Listing on our website and annual report as municipal members.
- Printed quarterly newsletter and weekly PBN e-update.

(For more information about the PBN membership options, visit <https://bit.ly/JoinPBN>)

617 Main Street, Buffalo, New York 14203 • Phone: (716) 852-3300  
[www.preservationbuffaloniagara.org](http://www.preservationbuffaloniagara.org) • [info@pbnsaves.org](mailto:info@pbnsaves.org)



# INVOICE

Amherst Historic Preservation Commission  
Town of Amherst  
c/o Sue Palmer

Invoice Date: November 11, 2023

Current Membership Level: Steward Circle (\$1,000)  
Current Expiration Date: 12/31/2023

| Description                 | # | Price        | Total           |
|-----------------------------|---|--------------|-----------------|
| Protector Circle membership | 1 | \$250.00     | \$250.00        |
|                             |   |              |                 |
|                             |   | <b>TOTAL</b> | <b>\$250.00</b> |

Thank you!

Attachment: membership invoice 2024\_1 (28306 : 2023 Budget)